


GENERAL NOTES:

1. THE LOWEST FLOOR ELEVATIONS OF ANY ENCLOSED SPACE (INCLUDING THE GARAGE OR BASEMENT) MUST BE AT LEAST TWO FEET ABOVE THE 100 YEAR FLOOD ELEVATION. THIS MINIMUM FLOOR ELEVATION IS CALLED THE FLOOD PROTECTION GRADE (FPG). HIGHER FINISHED FLOOR ELEVATIONS ARE REQUIRED IN SOME INSTANCES IN ORDER TO PROVIDE POSITIVE DRAINAGE TO SWALES AND STREETS.
2. ANY CRAWL SPACE LOCATED ON A LOT WITH FPG DESIGNATION SHALL MAINTAIN AN ELEVATION AT THE LOWEST POINT IN THE CRAWL SPACE OF 0.10 FEET ABOVE THE 100 YEAR FLOOD ELEVATION (BFE).
3. FILL MATERIAL FOR BUILDING PADS FOR THE FOUNDATIONS OF RESIDENTIAL STRUCTURES SHALL BE PLACED AFTER STRIPPING OF TOPSOIL AND SHALL BE COMPACTED TO 95% OF THE MAXIMUM DENSITY OBTAINABLE WITH THE STANDARD PROCTOR METHOD (ASTM D 698).

Standard Grading Plan Dwelling or Accessory Structures

No Scale




NOTE:

1. SOD REQUIRED IF LONGITUDINAL SLOPE IS 4% OR GREATER.
2. 16"x8" CONCRETE RIBBON REQUIRED IF LONGITUDINAL SLOPE IS LESS THAN 0.8%.
3. RIP-RAP OR EROSION CONTROL BLANKET REQUIRED ON SIDE SLOPES GREATER THAN 3:1. REFER TO EROSION/SEDIMENT CONTROL PLAN.

Section D-D Drainage Swales

Scale: 3/8" = 1'-0"




NOTE:

1. SOD REQUIRED IF LONGITUDINAL SLOPE IS 4% OR GREATER.
2. 16"x8" CONCRETE RIBBON REQUIRED IF LONGITUDINAL SLOPE IS LESS THAN 0.8%.
3. RIP-RAP OR EROSION CONTROL BLANKET REQUIRED ON SIDE SLOPES GREATER THAN 3:1. REFER TO EROSION/SEDIMENT CONTROL PLAN.

Typical Swale Cross Section

Scale: 1/2" = 1'-0"




NOTE:

1. STAKED SOD OR NORTH AMERICAN GREEN TEMPORARY EROSION CONTROL BLANKET SC-150 OR APPROVED EQUAL IF LONGITUDINAL SLOPE IS 2% TO 6%.
2. 16"x8" CONCRETE RIBBON REQUIRED BETWEEN LOTS 45 AND 46.

Typical Emergency Overflow Swale Cross Section


Scale: 1/2" = 1'-0"



1. Top of banks for basin within the floodway are at existing ground. No Fill is allowed within the limits of the Floodway.
2. Existing treeline along Schlensker Ditch and tributary banks are to remain undisturbed except for the location of the basin spillway.

Basin #1 Section A-A


No Scale



Basin #1 Spillway

No Scale

*Bridlewood #6 Basin outlet open channel*



Section B-B Interconnection Ditch

Scale: 3/8" = 1'-0"

1. BEGIN DITCH SECTION @ CRATER DRIVE CURB TURNOUT SWALE TIE-IN
2. END DITCH SECTION @ SOUTH SIDE OF PIPE 529

**Morley and Associates, Inc.**  
 Consulting Engineers/Surveyors/Architects  
 600 S.E. Sixth Street  
 Evansville, Indiana 47713  
 (812) 464-9585

All ideas, designs, calculations, and arrangements indicated or represented by this drawing are owned by and the property of Morley and Associates, Inc. and were created for the use and in connection with the specified project. None of such ideas, designs, calculations, or arrangements shall be used, copied, or reproduced in any form, or for any purpose whatsoever, without the written permission of Morley and Associates, Inc. Written dimensions on these drawings shall have precedence over all other dimensions and conditions on the job and Morley and Associates, Inc. must be notified of any variations from the dimensions and conditions shown by these drawings.

No.	By	Date	Description



Project: Bridlewood Subdivision Section 6  
 Sheet Title: Drainage/Grading Details  
 Scale: AS SHOWN  
 Designed By: R.S.L. Job Number: 5527-4(B)  
 Drawn By: G.A.M. Date: 4/9/03  
 File Name: J:\5527\Civil\5527det.dwg  
 Sheet Number: C-10