




RECEIVED BY THE VANDERBURGH COUNTY SUBVEYORS OFFICE ( ~ 7/21/5










# REINFORCED CONCRETE PIPE BEDDING

Scale: N.T.S.








SECTION B-B

### **SECTION A-A**


DIA.	WALL	G or T	WT. SEC.	Α	В	С	D	E	DIA.+1	R-1	R-2	SKIRT
12	2	1 1/2	530	4	24	48 7/8	72 7/8	24	13	10 1/16	9	3 1/2
15	2 1/4	2	740	6	27	46	73	30	16	12 1/2	11	3 1/2
18	2 1/2	2 1/2	990	9	27	46	73	36	19	15 1/2	12	4
21	2 3/4	2 1/4	1280	9	35	38	73	42	22	16 1/8	13	4
24	3	2 1/2	1520	9 1/2	43 1/2	30	73 1/2	48	25	16 11/16	14	4 1/2
27	3 1/4	2 1/2	1930	10 1/2	48	25 1/2	73 1/2	54	28	17 3/4	14 1/2	4 1/2
30	3 1/2	3	2190	12	54	19 3/4	73 3/4	60	31	18 5/16	15	5
33	3 3/4	3 3/8	3150	13 1/2	58 1/2	39 1/4	97 3/4	66	34	23 3/4	17 1/2	5 1/2
36	4	3 1/2	4100	15	63	34 3/4	97 3/4	72	37	24 1/16	20	5 1/2
42	4 1/2	3 3/4	5380	21	63	35	98	78	43	27 1/4	22	5 1/2
48	5	4 1/4	6550	24	72	26	98	84	49	28 1/8	22	5 3/4
54	5 1/2	4 3/4	8040	27	65	35	100	90	55	32 7/8	24	6 1/4
60	6	5	8750	30	60	39	99	96	61	36 3/4	24	6 3/4
66	6 1/2	5 1/2	10630	24	78	21	99	102	67	35 11/16	24	7 1/4
72	7	6	12520	34	78	21	99	108	73	38 5/8	24	7 3/4
78	7 1/2	6 1/2	14430	24	78	21	99	114	79	41 15/16	24	8 1/2
84	8	7	16350	24	78	21	99	120	85	44 13/16	24	9

Manufacture of end section is in accordance with applicable portions of A.S.T.M. specification C76.


# PRECAST CONCRETE END SECTION




STREET SIGNS



Scale: N.T.S.






1. 1/2" preformed expansion joint material at all P.C. and P.T. curb radii. 2. Tooled contraction joints at 10 ft. centers. Contraction joints to be a minimum 2" deep and 1/8" to 1/4" wide.


CONCRETE ROLL CURB AND GUTTER

Scale: N.T.S.




TYPICAL RESIDENTIAL CUL-DE-SAC


Scale: N.T.S.




### 29' RESIDENTIAL BITUMINOUS PAVEMENT WITH CONCRETE ROLL CURB & GUTTER Scale: N.T.S.



TYPICAL SWALE CROSS-SECTION





**INLET BOX TABLE TYPE** INLET 24" 30" 36" EJIW #7030 Type M2 Grate

**MANHOLE** EJIW #1020 Non-Paved Areas Type M2

**INLET NOTES:** All precast units shall conform to ASTM C-478. Inlets shall be backfilled with granular material and compacted in 8" loose lifts to 95% Standard Density

Casting shall be mastic sealed to precast unit. All connnecting pipes shall be grouted with a high strength, non-shrink grout.

per ASTM D698.

Frame & castings shown are the type & size required for the given box dimensions. Alternates shall be equal to those shown, including grate & opening sizes.

Front of Grate (F.G.) elevation 1/2" below pavement grade - Mastic seal casting

PLAN

per ASTM C-478

WWOLEDIE

AREA DRAIN/MANHOLE

PRECAST INLET BOX Scale: N.T.S.

CURB INLET

MAR 0 3 2015

This drawing and/or specifications is provided as an instrument of service provided by Cash Waggner & Associates, PC and is intended for use on this project only. All drawings, specifications, designs, models, ideas, calculations, and arrangements appearing herein constitutes the original and unpublished Work of and remains the property of Cash Waggner & Associates, PC. Any reproduction, use or disclosure of the proprietary information contained herein without the prior written consent of the Cash Waggner & Associates, PC is Written dimensions shown hereon shall take precedence over scaled dimensions. Contractors shall calculate and measure required dimensions. Notify Cash Waggner & Associates, PC with any variations in dimensions or conditions from those indicated on these drawings. This drawing was based on available information. Commencement of Work constitutes verification and acceptance of

Application of a material or equipment to Work installed by others constitutes acceptance of that Work and assumption of responsibility for satisfactory installation.





CASH WAGGNER & ASSOCIATES, PC CONSULTING ENGINEERS . LAND SURVEYORS

		No.	DATE	BY	DESCRIPTION
41.4.5	m	$\triangle$			
414 CITADEL CIRCLE SUITE B	Z		******		
VANSVILLE, IN 47715					
PH: 812.401.5561	S				
FAX: 812.401.5563	5				
SELL: 812.774.2988 E-MAIL: GMERITT@	Ш	$ \Delta $			
CASHWAGGNER.COM	吖				

'ROJECT NO.: 14-1948 DRAWN BY: G.A.M. FILENAME: 1948 Road Storm Dtls SCALE: As Shown

CAYMAN RIDGE - SECT. 4 KANSAS ROAD EVANSVILLE, INDIANA

ROAD & STORM SEWER DETAILS

12.02.14 DRAWING NO.: C-107


OF: 13

# CONSTRUCTION/STORMWATER POLLUTION PREVENTION PLAN (SWP3) NARRATIVE

A1. PLAN INDEX	
A. CONSTRUCTION PLAN ELEMENTS	LOCATION
A2. 11 BY 17-INCH PLAT SHOWING BUILDING LOT NUMBERS/BOUNDARIES AND ROAD LAYOUT/NAMES.:	TTACHMENTS
A3. NARRATIVE DESCRIBING NATURE AND PURPOSE:	THIS SHEET
A4. VICINITY MAP SHOWING PROJECT LOCATION:	THIS SHEET
A5. LEGAL DESCRIPTION OF THE PROJECT SITE:	TTACHMENTS
A6. LOCATION OF ALL LOTS AND PROPOSED SITE IMPROVEMENTS:	SHEET C-110
A7. HYDROLOGIC UNIT CODE (14 DIGIT):	THIS SHEET
A8. NOTATION OF ANY STATE OR FEDERAL WATER QUALITY PERMITS:	THIS SHEET
A9. SPECIFIC POINTS WHERE STORM WATER DISCHARGE WILL LEAVE THE SITE:	THIS SHEET
A10. LOCATIONS AND NAME OF ALL WETLANDS, LAKES AND WATERCOURSES ON AND ADJACENT TO THE SITE. THIS SHEET &	ATTACHMENTS
A11. IDENTIFICATION OF ALL RECEIVING WATERS:	THIS SHEET
A12. IDENTIFICATION OF POTENTIAL DISCHARGES TO GROUND WATER:	THIS SHEET
A13. 100 YEAR FLOODPLAINS, FLOODWAYS, AND FLOODWAY FRINGES:THIS SHEET & A	TTACHMENTS
A14. PRE-CONSTRUCTION AND POST CONSTRUCTION ESTIMATE OF PEAK DISCHARGE (10 YEAR EVENT):THIS SHEET & A	TTACHMENTS
A15. ADJACENT LAND USE, INCLUDING UPSTREAM WATERSHED:	"THIS SHEET
A16. LOCATIONS AND APPROXIMATE BOUNDARIES OF ALL DISTURBED AREAS:	EET & C-110
A17. IDENTIFICATION OF EXISTING VEGETATIVE COVER:	THIS SHEET
A18. SOILS MAP INCLUDING SOIL DESCRIPTIONS AND LIMITATIONS:	ATTACHMENTS
A19. LOCATIONS, SIZE AND DIMENSIONS OF PROPOSED-STORM WATER SYSTEMS:	SHEET C-110
A20. PLANS FOR ANY OFF-SITE CONSTRUCTION ACTIVITIES ASSOCIATED WITH THIS PROJECT :	THIS SHEET
A21. LOCATIONS OF PROPOSED SOIL STOCKPILES AND/OR BORROW/DISPOSAL AREAS:THIS SH	EET & C-110
A22. EXISTING SITE TOPOGRAPHY AT AN INTERVAL APPROPRIATE TO INDICATE DRAINAGE PATTERNS:	SHEET C-110
A23. PROPOSED FINAL TOPOGRAPHY AT AN INTERVAL APPROPRIATE TO INDICATE DRAINAGE PATTERNS:	SHEET C-110
B. STORMWATER POLLUTION PREVENTION PLAN:	LOCATION
B1. DESCRIPTION OF POTENTIAL SOURCES ASSOCIATED WITH CONSTRUCTION ACTIVITIES:	THIS SHEET
DO OFFICIAL DESCRIPTING STEPRINATED OUGLITY MEASURE IMPLEMENTED DELATIVE TO LAND DISTURBING ACTIVITIES:	THIS SHEET

B. STORMWATER POLLUTION PREVENTION PLAN:	
B1. DESCRIPTION OF POTENTIAL SOURCES ASSOCIATED WITH CONSTRUCTION ACTIVITIES:THIS SHEET	
B2. SEQUENCE DESCRIBING STORMWATER QUALITY MEASURE IMPLEMENTED RELATIVE TO LAND DISTURBING ACTIVITIES:THIS SHEET	
B3. STABLE CONSTRUCTION ENTRANCE LOCATIONS AND SPECIFICATIONS:	٠
B4. SEDIMENT CONTROL MEASURES FOR SHEET FLOW AREAS:	•
B5. SEDIMENT CONTROL MEASURES FOR CONCENTRATED FLOW:	-
B6. STORM SEWER INLET PROTECTION MEASURE LOCATION AND SPECIFICATION:	
B7. RUNDFF CONTROL MEASURES:	-
B8. STORMWATER DUTLET PROTECTION SPECIFICATIONS:	-
B9. GRADE STABILIZATION STRUCTURE LOCATIONS AND SPECIFICATIONS:	-
B10. LOCATION, DIMENSIONS, SPECIFICATION, AND CONSTRUCTION DETAILS OF EACH STORMWATER QUALTIY MEASURE:THIS SHEET	Г
B11. TEMPORARY SURFACE STABILIZATION METHODS APPROPRIATE FOR EACH SEASON:	ŗ
B12. PERMANENT SURFACE STABILIZATION SPECIFICATIONS:	ŗ
B13. MATERIAL HANDLING AND SPILL PREVENTION:	ſ
B14. MONITORING AND MAINTENANCE GUIDELINES FOR POLLUTION PREVENTION MEASURES:	Γ
B15. EROSION & SEDIMENT CONTROL SPECIFICATIONS FOR INDIVIDUAL BUILDING LOTS:	Γ

C1. DESCRIPTION OF POLLUTANTS AND THEIR SOURCES ASSOCIATED WITH THE PROPOSED LAND USE: .....



### A. CONSTRUCTION PLAN ELEMENTS

- A1. PLAN INDEX SHOWING LOCATIONS OF REQUIRED ITEMS:
- This sheet. A2. 11 BY 17-INCH PLAT SHOWING BUILDING LOT NUMBERS/BOUNDARIES AND ROAD LAYOUT/NAMES;
- See attached primary plat. A3. NARRATIVE DESCRIBING NATURE AND PURPOSE:
- Develop a single-family residential subdivision. The earthwork, utilities and streets for the subdivision will be constructed in one phase. The existing detention basin located at the northeast corner of the property will be utilized as a sediment basin during construction.
- A4. VICINITY MAP SHOWING PROJECT LOCATION:
- See lower left hand corner of this sheet. A5. LEGAL DESCRIPTION OF THE PROJECT SITE:
- The site is located in the SE 1/4 and SW 1/4 of Sec. 22, Township 5-S, Range 10 West; Center Township. Approximate coordinates: Latitude = 38-deg 04' 01" N; Longitude =87-deg 30' 57" W.
- A6. LICATION OF ALL LOTS AND PROPOSED SITE IMPROVEMENTS: - This project will consist of 25 single-family residential lots and their associated road and utility
- improvements. A7. HYDROLOGIC UNIT CODE (14 DIGIT):
- 05140202040070; Bluegrass Creek Firlick Creek
- A8. NOTATION OF ANY STATE OR FEDERAL WATER QUALITY PERMITS: - None anticipated
- A9. SPECIFIC POINTS WHERE STORM WATER DISCHARGE WILL LEAVE THE SITE; - All stormwater runoff will travel to the existing detention basin located at the northeast corner of the project before leaving the site. The primary spillway of the detention basin then discharges into an existing ditch that flows east thru Stonecreek PUD then discharges into Firlick Creek.
- A10. LOCATIONS AND NAME OF ALL WETLANDS, LAKES AND WATERCOURSES ON AND ADJACENT TO THE SITE: - No wetlands are located within the project boundaries (See attached exhibit)
- A11. IDENTIFICATION OF ALL RECEIVING WATERS: - Firlick Creek.
- A12. IDENTIFICATION OF POTENTIAL DISCHARGES TO GROUND WATER: - There is no apparent potential for direct discharge to ground water via sinkholes, abandoned
- wells or drywells. A13. 100 YEAR FLOODPLAINS, FLOODWAYS, AND FLOODWAY FRINGES - No portion of the project boundary lies within the Special Flood Hazard Area, Zone 'AE', as said tract plots on the National Flood Insurance Program's Flood Insurance Rate Map for Vanderburgh County,
- Indiana, Community Panel Map No. 18163C0109D, dated March 17, 2011. A14. PRE-CONSTRUCTION AND POST CONSTRUCTION ESTIMATE OF PEAK DISCHARGE (10 YEAR EVENT): - Calculations by the Rational Method indicate a Pre-Construction Q(10) = 17.16-cfs and a
- Post-Construction O(10) = 18.78-cfs.
- A15. ADJACENT LAND USE, INCLUDING UPSTREAM WATERSHED - Immediately adjacent properties are residential to the north, south, east and west.
- A16. LOCATIONS AND APPROXIMATE BOUNDARIES OF ALL DISTURBED AREAS: - The entire site will be disturbed during construction of this project.
- A17. IDENTIFICATION OF EXISTING VEGETATIVE COVER:
- The proposed disturbed area is a cultivated field. A18. SOILS MAP INCLUDING SOIL DESCRIPTIONS AND LIMITATIONS:
- According to the USDA's Soil Survey of Vanderburgh County Indiana, the following soils exist on-site: SOILS DESCIPTIONS

#### He Henshaw Silt Loam

HoB2 Hosmer Silt Loam, 2 - 6 percent slopes, eroded

HoC3 Hosmer Silt Loam, 6 - 12 percent slopes, severely eroded

#### Wm Wilbur Silt Loam

He HoB2 HoC3	Shallow Excavations Very limited Very limited Very limited	Very limited Very limited Very limited Very limited
Wm	Very limited	Very limited

- A19. LOCATIONS, SIZE AND DIMENSIONS OF PROPOSED-STORM WATER SYSTEMS: - A drainage swale and storm sewer network will be installed within the development to capture storm runoff and convey it to the detention basin. The detention basin primary spillway discharges to an existing ditch that flows east and discharges into Firlick Creek. See Sheet C-110 for locations, size and dimensions.
- A20. PLANS FOR ANY OFF-SITE CONSTRUCTION ACTIVITIES ASSOCIATED WITH THIS PROJECT : No off-site construction is anticipated for this project.
- A21. LOCATIONS OF PROPOSED SOIL STOCKPILES AND/OR BORROW/DISPOSAL AREAS:
- Proposed soil stockpile location is shown on Sheet C-110. A22, EXISTING SITE TOPOGRAPHY AT AN INTERVAL APPROPRIATE TO INDICATE DRAINAGE PATTERNS:
- See the SWP3 drawing, Sheet C-110, for existing contours and/or spot elevations. A23. PROPOSED FINAL TOPOGRAPHY AT AN INTERVAL APPROPRIATE TO INDICATE DRAINAGE PATTERNS: - See the SWP3 drawing, Sheet C-110, for proposed contours and/or spot elevations.

### MAINTENANCE NOTES

- SILT FENCE MAINTENANCE REQUIREMENTS
- 1. INSPECT THE SILT FENCE PERIODICALLY AND AFTER EACH STORM EVENT. 2. IF FENCE FABRIC TEARS, STARTS TO DECOMPOSE, OR IN ANY WAY BECOMES INEFFECTIVE,
- REPLACE THE AFFECTED PORTION IMMEDIATELY.
- 3. REMOVE DEPOSITED SEDIMENT WHEN IT REACHES HALF THE HEIGHT OF THE FENCE AT ITS LOWEST POINT OR CAUSING THE FABRIC TO BULGE.
- 4. TAKE CARE TO AVOID UNDERMINING THE SILT FENCE DURING CLEAN OUT. 5. AFTER THE CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED, REMOVE THE FENCE AND
- SEDIMENT DEPOSITS, BRING THE DISTURBED AREA TO GRADE AND STABILIZE.
- TEMPORARY SEDIMENT BASIN MAINTENANCE REQUIREMENTS 1. INSPECT TEMPORARY SEDIMENT TRAPS AFTER EACH STORM EVENT AND IMMEDIATELY REPAIR
- ANY EROSION AND PIPING HOLES. 2. REMOVE SEDIMENT WHEN IT HAS ACCUMULATED TO ONE-HALF THE DESIGN DEPTH.
- 3. REPLACE SPILLWAY GRAVEL FACING IF CLOGGED.
- 4. INSPECT VEGETATION AND RE-SEED IF NECESSARY 5. CHECK THE SPILLWAY DEPTH PERIODICALLY TO INSURE A MINIMUM OF 1.5 FT. DEPTH FROM
- THE LOWEST POINT OF THE SETTLED EMBANKMENT TO HIGHEST POINT OF THE SPILLWAY CREST AND FILL ANY LOW AREA TO MAINTAIN DESIGN ELEVATION. 6. PROMPTLY REPLACE ANY DISPLACED RIPRAP BEING CAREFUL THAT NO STONES IN THE
- SPILLWAY ARE ABOVE DESIGN GRADE. 7. AFTER ALL DISTURBED AREAS HAVE BEEN STABILIZED, REMOVE THE STRUCTURE AND SEDIMENT. SMOOTH THE SITE TO BLEND WITH ADJOINING AREAS, AND STABILIZE.
- TEMPORARY GRAVEL CONSTRUCTION ENTRANCE MAINTENANCE REQUIREMENTS 1. INSPECT ENTRANCE PAD AND SEDIMENT DISPOSAL AREA WEEKLY AND AFTER STORM EVENTS
- 2. RESHAPE PAD AS NEEDED FOR DRAINAGE AND RUNOFF CONTROL.
- 3. TOPDRESS WITH CLEAN STONE AS NEEDED.
- 4. IMMEDIATELY REMOVE MUD AND SEDIMENT TRACKED OR WASHED ONTO PUBLIC ROADS BY BRUSHING OR SWEEPING. BULK CLEARING OF ACCUMULATED SEDIMENT SHALL NOT
- INCLUDE FLUSHING WITH WATER. 5. REPAIR ANY BROKEN ROAD PAVEMENT IMMEDIATELY.
- RIPRAP MAINTENANCE REQUIREMENTS 6. INSPECT PERIODICALLY FOR DISPLACED ROCK MATERIAL, SLUMPING, AND EROSION AT EDGES ESPECIALLY DOWN STREAM OR DOWN SLOPE.

- B. STORMWATER POLLUTION PREVENTION PLAN CONSTRUCTION COMPONENT
- B1. DESCRIPTION OF POTENTIAL POLLUTANT SOURCES ASSOCIATED WITH CONSTRUCTION ACTIVITIES. - Fuel and lubricants from machinery, waste from concrete truck washout, sanitary waste from latrines, construction waste, domestic garbage, sedimentation from storm water
- runoff and vehicle tracking, windborne dust, and fertilizers from seeding operations. B2. SEQUENCE DESCRIBING STORMWATER QUALITY MEASURE IMPLEMENTED RELATIVE TO LAND DISTURBING ACTIVITIES:

CONSTRUCTION PHASE (SPECIFIC ACTIVITIES OR EROSION CONTROL PRACTICES)	CONSTRUCTION SCHEDULE CONSIDERATIONS
PRE-CONSTRUCTION ACTIONS (EVALUATION/PROTECTION OF IMPORTANT SITE CHARACTERISTICS)	BEFORE CONSTRUCTION, EVALUATE, MARK, AND PROTECT VEGETATION SUITABLE FOR FILTER STRIPS, ESPECIALLY IN PERIMETER AREAS.
INSTALL PERIMETER BMPS * (CONSTRUCTION EXITS, FILTER STRIPS, SILT FENCE, DROP INLET PROTECTION, EQUIPMENT PARKING AREAS)	INSTALL GRAVEL ENTRANCE/EXIT; INSTALL SILT FENCE ON THE NORTH AND SOUTH PROPERTY LINES TO PREVENT SEDIMENT FROM EXITING THE SITE.
PREPARE SITE FOR CONSTRUCTION * (SOIL STOCKPILES AND TEMPORARY SEDIMENT BASIN)	INFORM ALL CONTRACTORS OF AREAS TO BE PROTECTED. IF STOCKPILING, IMMEDIATELY AFTER TEMPORARY SEED AND INSTALL SEDIMENT BARRIERS AROUND THE PERIMETER. THE PROPOSED DETENTION BASIN WILLL BE UTILIZED AS TEMPORARY SEDIMENT BASIN DURING CONSTRUCTION.
RUNOFF CONTROL * (ROCK CHECK DAMS, DIVERSIONS, PERIMETER DIKES, OUTLET PROTECTION)	INSTALL ENERGY DISSIPATERS AT THE OUTLETS OF ALL FES STRUCTURES IMMEDIATELY AFTER INSTALLATION. INSTALL ROCK CHECK DAMS IMMEDIATELY AFTER SWALES HAVE BEEN CONSTRUCTED.
RUNOFF CONVEYANCE SYSTEMS * (STABILIZE SWALES, STORM DRAINS, INLET AND OUTLET PROTECTION, CHANNELS)	STABILIZE SWALES IMMEDIATELY AFTER CONSTRUCTION WITH PERMANENT SEEDING. INSTALL INLET AND OUTLET PROTECTION IMMEDIATELY AFTER CONSTRUCTION OF STORM SEWER STRUCTURES.
LAND CLEARING AND GRADING * (CUTTING/FILLING, GRADING DRAINS, SEDIMENT TRAPS, BARRIERS, DIVERSIONS, SURFACE ROUGHENING)	BEGIN MAJOR CLEARING AND GRADING AFTER INSTALLING THE KEY SEDIMENT AND RUNOFF CONTOL MEASURES. CLEAR BORROW AND DISPOSAL AREAS AS NEEDED. INSTALL ADDITIONAL CONTROL MEASURES AS GRADING PROGRESSES.
SURFACE STABILIZATION * (TEMPORARY AND PERMANENT SEEDING, MULCHING, SODDING, RIP-RAP)	APPLY TEMPORARY OR PERMANENT STABILIZATION MEASURES IMMEDIATELY ON ALL DISTURBED AREAS WHERE WORK IS DELAYED OR COMPLETED.
BUILDING CONSTRUCTION * (BUILDING, UTILITIES, PAVING)	INSTALL NECESSARY EROSION AND SEDIMENT CONTROL PRACTICES AS WORK TAKES PLACE.
LANDSCAPING AND FINAL STABILIZATION * (TOPSOIL, TREES, AND SHRUBS, PERMANENT SEEDING, MULCHING, SODDING, RIP-RAP)	STABILIZE ALL OPEN AREAS INCLUDING BORROW AND SPOIL AREAS. REMOVE TEMPORARY CONTROL MEASURES AND STABILIZE.

- B3. STABLE CONSTRUCTION ENTRANCE LOCATIONS AND SPECIFICATIONS: - A temporary construction drive (large sites more than 2 acres) and equipment staging area shall be installed at the commencement of construction activities in accordance with the
- Indiana Storm Water Quality Manual. Refer to Sheet C-110 for suggested locations. B4. SEDIMENT CONTROL MEASURES FOR SHEET FLOW AREAS: - During excavation and underground utility installation, proposed swales and silt fence will be utilized on the north and south perimeters of the site to slow and filter the storm water runoff generated from this project. Filter strips and silt fence shall be installed per the Indiana Storm Water Quality
- Manual. Refer to Sheet C-110 for locations. All storm water runoff from this site shall be diverted to the existing detention basin which will be utilized as a sediment basin during construction. B5. SEDIMENT CONTROL MEASURES FOR CONCENTRATED FLOW AREAS: - Immediately after swales are constructed, permanent seeding shall be applied and rock check dams
- installed. Once stabilized, these vegetated swales will slow and filter the runoff before leaving the site. B6. STORM SEWER INLET PROTECTION MEASURE LOCATION AND SPECIFICATIONS: Proposed curb inlets shall be protected with drop inlet protection devices. Refer to Sheet C-109 for
- locations. B7. RUNOFF CONTROL MEASURES: - Rock check dams will be utilized to reduce erosion in the proposed swales by slowing the velocity of the
- runoff. Rock check dams shall be installed in accordance with the Indiana Storm Water Quality Manual. Swales #1, #2 and #3 shall be utilized as temporary diversion ditches during construction to direct water to the sediment basin.
- BB, STORM WATER DUTLET PROTECTION SPECIFICATIONS: - An energy dissipater shall be installed at FES #510 to reduce the velocity of the storm water flow.
- The energy dissipators shall be installed in accordance with the Indiana Storm Water Quality Manual. B9. GRADE STABILIZATION STRUCTURE LOCATIONS AND SPECIFICATIONS:
- None required. B10. LOCATION, DIMENSIONS, SPECIFICATION, AND CONSTRUCTION DETAILS OF EACH STORMWATER QUALITY MEASURE: Refer to the SWP3 drawings for locations of the respective control measures. Dimensions, specifications, and details of the measures are depicted in the Indiana Storm Water Quality
- Manual. Other practices which may be implemented shall be utilized and installed in accordance with the manufacturer's instructions. See Sheet C-112 for details.
- B11, TEMPORARY SURFACE STABILIZATION METHODS APPROPRIATE FOR EACH SEASON: The Contractor shall seed and mulch all disturbed areas when construction activities are expected to cease for a period of more than 15 days. Straw/hay mulch shall be applied at a rate of 2 tons/acre and shall be
- anchored with a mulch anchoring tool or farm disk. Seeding requirements shall be in accordance with Table 1, located in Chapter 7, page 32 of the Indiana Storm Water Quality Manual, which is summarized below. Table 1. Temporary Seeding Specifications

Seed Species *	Rate/acre	Planting depth	Optimum dates **
Wheet or Rye	150 lbs.	1 to 1-1/2 in.	9/15 to 10/30
Spring Oats	100 lbs.	1 in.	3/1 to 4/15
Annual Ryegrass	40 lbs.	1/4 in.	3/1 to 5/1 8/1 to 9/1
German Millet	40 lbs.	1 to 2 in.	5/1 to 6/1
Sudangrass	35 lbs.	1 to 2 in.	5/1 to 7/30
Buckwheat	60 lbs.	1 to 2 in.	4/15 to 6/1
Corn (broadcast)	300 lbs.	1 to 2 in.	5/11 to 8/10
Sorghum	35 lbs.	1 to 2 in.	5/1 to 7/15

- \* Perennial species may be used as a temporary cover, especially if the areas to be seeded will remain idle for more than 1 year. \*\* Seeding done outside the optimum seeding dates increases the chances of seeding failure. Dates may be extended or
- shortened based on the location of the project site within the state. - The seed bed shall be prepared by applying 400-600 lbs per acre of 12-12-12 fertilizer and working 2-4 inches into the soil and mulching material applied at the rate of 2 tons per acre. - Dormant & Frost Seeding should be utilized for seeding when temperatures are too low for
- germination to occur. B12. PERMANENT SURFACE STABILIZATION SPECIFICATIONS: - The Contractor shall fertilize, seed and mulch all disturbed areas when final grading and land disturbing operations are complete. Seeding requirements shall be in accordance with
- Table 1, located in Chapter 7, pages 38-39 of the Indiana Storm Water Quality Manual, shown to the right. - The seed bed shall be prepared by applying 400-600 lbs per acre of 12-12-12 fertilizer and working 2-4 inches into the soil and apply straw/hay mulch at the rate of 2 tons per acre.
- Optimum dates for permanent seeding are March 1 May 10 and August 10 September 30. - Temporary seeding should be considered between May 10 and August 10. - Dormant & Frost Seeding should be utilized when temperatures are too low for germination to occur, October 1 - May 9.
- B13. MATERIAL HANDLING AND SPILL PREVENTION: - The Contractor shall notify the Indiana Department of Environment Management (1.800.233.7745) when spills occur and threaten water quality due to storm water runoff.
- All materials used on-site shall be stored in an orderly manner and approved containers. Materials shall be kept in their original packaging with the manufacturer's labels until ready for installation. - All materials shall be used, installed and disposed of in accordance with its manufacturer's instructions
- and as required by governing agencies. - The Contractor shall utilize re-sealable containers when storing unused materials susceptible to spillage. - The Contractor shall keep manufacturer's labels and Material Safety Data Sheets (MSDS) on site. - The Contractor shall monitor equipment and their parking areas for leaks.
- B14. MONITORING AND MAINTENANCE GUIDELINES FOR POLLUTION PREVENTION MEASURES - All stormwater quality measures shall be inspected and maintained in accordance with its respective manufacturer's recommendations and the Indiana Storm Water Quality Manual. A self-monitoring program that includes the following must be implemented:
- A trained individual shall perform a written evaluation of the project site: \* By the end of the next business day following each 1/2-inch storm event; and \* at a minimum of one time per week.
- \* The maintenance of existing stormwater quality measures to ensure they are functioning properly; and \* Identify additional measures necessary to remain in compliance with all applicable statutes and rules. Written evaluation reports must include:

\* Details of corrective actions recommended and completed.

\* The name of the individual performing the evaluation;

The evaluation must address

- \* The date of the evaluation \* Problems identified at the project site; and
- NO. DATE BY 14-1948 DESIGNED BY: G.A.M. DRAWN BY: G.A.M. FILENAME: SWP3 Narrative

SWP3 NARRATIVE

CAYMAN RIDGE - SECT. 4

KANSAS ROAD

EVANSVILLE, IN

4. Tall fescue \*\*

B15. EROSION & SEDIMENT CONTROL SPECIFICATIONS FOR INDIVIDUAL BUILDING LOTS: - Individual lot Owners/Developers shall comply with Best Management Practices (BMPs) outlined in this plan. In addition, lot Owners/Developers shall be responsible for implementing and maintaining BMPs for their respective lots including, but not limited to: \* Install/maintain a stable construction site access. \* Install/maintain appropriate perimeter BMPs prior to land disturbance.

\* Stabilize all areas outside the lot which were disturbed as a result of the subject lot development.

(i.e. silt fence, straw bales, vegetated filter strips, etc) \* Clean-up of sediment that may get tracked or washed onto roads

C. STORMWATER POLLUTION PREVENTION PLAN - POST CONSTRUCTION COMPONENT

- C1. DESCRIPTION OF POLLUTANTS AND THEIR SOURCES ASSOCIATED W/ THE PROPOSED LAND USE: - Oil, grease, antifreeze, brake fluid, brake dust, rubber fragments, gasoline, diesel fuel, and other hydrocarbons, and metals from vehicular sources. - Grit (sediment) from wearing of the road surface and falling off vehicular sources.
- Trash, bacteria and biological agents in trash, from littering or improper disposal or storage. - Pesticides, herbicides, and fertilizers from lawn/landscaping maintenance applications. - Elevated receiving water temperatures from stormwater runoff contact with impervious surfaces. C2. SEQUENCE DESCRIBING STORMWATER QUALITY MEASURE IMPLEMENTATION:
- Site monitoring for trash, debris, and deposited pollutants shall be a daily routine. - Once construction is complete, permanent seeding will be applied to the entire disturbed area excluding the asphalt roadways.
- The use of grass lined swales and vegetated filters are existing and will remain a permanent aspect of the site. - Absorption materials used to clean up hydrocarbon puddles shall be approved by the EPA. - Disposal of all trash, debris, and pollutants shall be in a manner approved by their
- their repsective governmental agencies. C3. DESCRIPTION OF PROPOSED POST CONSTRUCTION STORMWATER QUALITY MEASURES: - The lot owner shall monitor the pavement for pollutants deposited from vehicular sources. The lot owner shall use approved absorbtion materials to clean up such hydrocarbon pollutants.
- The lot owner shall periodically monitor the site for trash, debris, and grit deposited on site. The lot owner shall pick up debris and dispose of in an approved manner. - The lot owner shall minimize lawn/landscaping chemical applications.
- The detention basin will allow sediment in the runoff entering the basin time to settle out prior to being discharged. The existing & proposed vegetated areas will cause infiltration of runoff and trap pollutants
- before they leave the site. - The vegetated ditches and detention basin will be utilized to filter pollutants, reduce runoff velocities, and help lower the temperature of the runoff before it reaches the receiving water.
- The storm sewer pipe network will help lower the temperature of the storm water runoff before it discharges into the receiving water. - The combination of grass lawns, vegetated swales and detention basin will be utilized to meet the minimum requirement of 80% Total Suspended Solids (TSS) removal prior to

installed in accordance with the manufacturer's instructions.

- leaving the site. (See attached literature) C4. LOCATION, DIMENSIONS, SPECIFICATIONS & CONSTRUCTION DETAILS OF EACH STORMWATER QUALTIY MEASURE Refer to the Sheet C-111 for locations of the respective control measures. Dimensions, specifications, and details of the measures are depicted in the Indiana Storm Water Quality Manual and Sheet C-112. Other practices which may be implemented shall be utilized and
- C5. DESCRIPTION OF MAINTENANCE GUIDELINES FOR PROPOSED POST CONSTRUCTION WATER QUALITY MEASURES: - Site monitoring for trash, debris, and deposited pollutants shall be a daily routine and shall be the responsibility of the lot owners.
- The use of grass-lined swales and vegetated filters are existing and will remain a permanent aspect of the site. The lot owners shall monitor these areas for trapped pollutants and erosion. - The respective lot owners shall maintain all storm drainage features (i.e. swales, detention basin, etc.) in accordance with the recorded plat covenants.

#### Table 1. Permanent Seeding Recommendations

Open Low-Maintenance Areas (remaining idle more than six months)

Seed Mixtures	Pure Live Seed	Optimum 300 pr	
1. Perennial ryegrass	70 lbs.	5.6 to 7.0	
- white clover *	2 lbs.		
2. Perennial ryegrass	70 lbs.	5.6 to 7.0	
- tall fescue **	50 lbs.	3.0 to 7.0	
3. Tall fescue **	70 lbs.	5.5 to 7.5	
- white clover *	2 lbs.	5.5 to 7.5	
Steep Banks and Cuts, Low	-Maintenance Areas	(not mowed)	
Seed Mixtures	Rate/acre Pure Live Seed	Optimum Soil pl	

Seed Mixtures	Rate/acre Pure Live Seed	Optimum Soil pl	
1. Smooth brome grass	35 lbs.	5.5 to 7.0	
- red clover *	20 lbs.	3.5 to 7.0	
2. Tall fescue **	50 lbs.	F F 4 - 7 F	
- white clover *	2 lbs.	5.5 to 7.5	
3. Tall fescue **	50 lbs.	5.5 to 7.5	
- red clover *	20 lbs.		
4. Orchard grass	30 lbs.		
- red clover *	20 lbs.	5.6 to 7.0	
- white clover *	2 lbs.		
5. Crownvetch *	12 lbs.	5.6 to 7.0	
- tall fescue **	30 lbs.	3.0 to 7.0	

Seed Mixtures	Rate/acre Pure Live Seed	Optimum Soil pl
1. Bluegrass	140 lbs.	5.5 to 7.0
2. Perennial ryegrass (turf type)	60 lbs. 90 lbs.	5.6 to 7.0
3. Tall fescue (turf type) ** - bluegrass	170 lbs. 30 lbs.	5.6 to 7.5

Optimum Soil pH Pure Live Seed Perennial ryegrass Kentucky bluegrass - smooth bromegrass 5.5 to 7.5 perennial ryegrass - white clover \*\* 5.5 to 7.5

 perennial ryegrass Kentucky bluegras \* For best results: (a) legume seed should be inoculated; (b) seeding mixtures containing legumes should preferably be spring-seeded, although the grass may be fall-seeded and the legume frost-seeded; and (c) if legumes are

fall-seeded, do so in early fall. \*\* Tall fescue provides little cover for, and may be toxic to some species of wildlife. The IDNR recognizes the need for additional research on alternatives such as buffalograss, orchardgrass, smooth bromegrass, and switchgrass. This research, in conjunction with demonstration areas, should focus on erosion control

characteristics, wildlife toxicity, turf durability and drought resistance. MAR 0 3 2015

11.07.14 DRAWING No.: C-109

provided by Cash Waggner & Associates, PC and is intended for use on this project only. All drawings, specifications, designs, models, ideas, calculations and arrangements appearing herein constitutes the original and unpublished work of and remains the property of Cash Waggner & Associates, PC. Any reproduction, use or disclosure of the proprietary information contained herei without the prior written consent of the Cash Waggner & Associates, PC is Written dimensions shown hereon shall take precedence over scaled dimensions. Contractors shall calculate and measure required dimensions. Notify Cash Waggner & Associates, PC with any variations in dimensions or conditions from those indicated on these drawings. This drawing was based on available ation. Commencement of Work constitutes verification and acceptance of

Application of a material or equipment to Work installed by others constitutes acceptance of that Work and assumption of responsibility for satisfactory

his drawing and/or specifications is provided as an instrument of se

C. POST CONSTRUCTION STORMWATER POLLUTION PREVENTION PLAN:

C2. SEQUENCE DESCRIBING STORMWATER QUALITY MEASURE IMPLEMENTATION:

C3. DESCRIPTION OF PROPOSED POST CONSTRUCTION STORMWATER QUALITY MEASURES:

7 Nov 14 SIGNATURE

DATE

<u>LDCATION</u>




& ASSOCIATES, PC

CONSULTING ENGINEERS . LAND SURVEYORS

414 CITADEL CIRCLE SUITE B EVANSVILLE, IN 47715 PH: 812.401.5561 FAX: 812.401.5563 CELL: 812.774.2988 E-MAIL: GMERITT@ | 7 CASHWAGGNER.COM

LAYOUT TAB: SWP3 Narr



RECEIVED BY THE
VANDERBURGH COUNTY
SURVEYOR'S OFFICE

A T TTTLE

