
Walmart > SUPERCENTER NO. 3374-00

C-182-SGL-QL

Located At State Route 57 and E. Boonville/New Harmony Road City of Evansville, Vanderburgh County, Indiana




THE SITEWORK FOR THE WAL-MART PORTION OF THIS PROJECT SHALL MEET OR EXCEED THE "SITE SPECIFIC SPECIFICATIONS." ALL NECESSARY INSPECTIONS AND/OR CERTIFICATIONS REQUIRED BY CODES AND/OR UTILITY SERVICE COMPANIES SHALL BE PERFORMED PRIOR TO CONTRACT COMPLETION AND THE FINAL

ALL ROADWAY AND PARKING LOT IMPROVEMENTS SHALL BE COMPLETED IN ACCORDANCE WITH THE APPLICABLE SECTIONS OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, DEPARTMENT OF TRANSPORTATION, STATE OF ILLINOIS, LATEST EDITION. ALL UNDERGROUND IMPROVEMENTS SHALL BE CONSTRUCTED AND TESTED IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS FOR WATER AND SEWER MAIN CONSTRUCTION IN ILLINOIS AND STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, DEPARTMENT OF TRANSPORTATION, STATE OF ILLINOIS. IN THE EVENT OF CONFLICTING GUIDELINES, THE MORE RESTRICTIVE SHALL GOVERN.

ALL ELEVATIONS ARE RELATIVE TO NGVD29 DATUM. THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES AND, WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. CONTRACTOR SHALL VERIFY THE LOCATION AND ELEVATION OF ALL UTILITIES PRIOR TO COMMENCING WORK AND WILL BE RESPONSIBLE FOR ANY DAMAGE THERETO. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY AT LEAST 48 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATIONS OF UTILITIES. CONTRACTOR TO IMMEDIATELY NOTIFY ENGINEER OF ANY DISCREPANCIES BETWEEN EXISTING "PLAN" ELEVATIONS AND EXISTING "SITE" ELEVATIONS PRIOR TO COMMENCING OF WORK. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED

IMPROVEMENTS SHOWN ON THESE PLANS. THE TOPOGRAPHY SURVEY FOR THIS PROJECT IS BASED ON A FIELD SURVEY PREPARED BY MANHARD CONSULTING, LTD. AND WAS PERFORMED ON FEBRUARY 18, 2014. THE CONTRACTOR SHALL VERIFY THE EXISTING CONDITIONS PRIOR TO CONSTRUCTION AND SHALL IMMEDIATELY NOTIFY MANHARD CONSULTING, LTD. AND THE CLIENT IN WRITING OF ANY DIFFERING CONDITIONS.



Manhard

900 Woodlands Parkway, Vernon Hills, IL 60061 tel: [847] 634 5550 fax: [847] 634 0095 www.manhard.com Civil Engineers · Surveyors · Water Resources Engineers · Water & Wastewater Engineers Construction Managers · Environmental Scientists · Landscape Architects · Planners

INDEX OF SHEETS

SHEET	NO. DESCRIPTION
1	TITLE SHEET
2	SWPPP NOTES
3	SWPPP IMPLEMENTATION SEQENCE AND LIMITS OF WORK
4	PHASE 1 EROSION AND SEDIMENTATION CONTROL PLAN
5	THE PROPERTY OF THE PROPERTY O
6	EROSION AND SEDIMENTATION CONTROL DETAILS
7	EROSION AND SEDIMENTATION CONTROL DETAILS
8	EROSION AND SEDIMENTATION CONTROL DETAILS
9	EROSION AND SEDIMENTATION CONTROL DETAILS
10	ALTA-ACSM LAND TITLE SURVEY (NOT INCLUDED)
11	PLAT OF SUBDIVISION (NOT INCLUDED)
_	EXISTING CONDITIONS AND DEMOLITION PLAN
13	OVERALL SITE DIMENSIONAL AND PAVING PLAN
14	SITE DIMENSIONAL AND PAVING PLAN - WEST
15	SITE DIMENSIONAL AND PAVING PLAN - EAST
16	OVERALL GRADING PLAN - REVISED SHEET 7/9/2015
17	GRADING PLAN - WEST
18	GRADING PLAN — EAST
19	OVERALL UTILITY PLAN
20	UTILITY PLAN - WEST
21	UTILITY PLAN — EAST
22	
23	
<u>24</u>	LIGHTING PLAN (NOT INCLUDED)
<u>25</u>	IRRIGATION PLAN (NOT INCLUDED)
<u>26</u>	IRRIGATION DETAILS (NOT INCLUDED)
27	IRRIGATION DETAILS (NOT INCLUDED)
28	2-11-5 SHEET 7/9/2015
29	
30	CONSTRUCTION DETAILS - NOT SCANNED
31	CONSTRUCTION DETAILS - NOT SCANNED
32	CONSTRUCTION DETAILS - NOT SCANNED
33	CONSTRUCTION DETAILS - NOT SCANNED
34	CONSTRUCTION DETAILS
35	CONSTRUCTION DETAILS - NOT SCANNED
36	CONSTRUCTION DETAILS - NOT SCHNED
37	
	THIS PROJECT
	OTHERS RESPONSIBILITY—
TH GAS COMPANY ARE COMPLETED	GAS COMPANY RESPONSIBILITY - SERVICE FROM THE POINT OF CONNECTION AT THE EXISTING LINE SERVICE FROM THE POINT OF CONNECTION AT THE EXISTING LINE SERVICE FROM THE POINT OF METER WILL BE BY THE GAS.
ON THE PLANS	UP TO AND INCLUDING SETTING OF METER WILL BE BY THE GAS COMPANY

JTILITY/ GOVERNING AGENCIES CONTACTS	CONTRACTOR RESPONSIBILITY-	OTHERS RESPONSIBILITY-	
AS: ECTREN GAS O BOX 209 VANSVILLE, IN 47702 HONE: 812-491-5010 CONTACT: BRAD VANBIBBER	TO ENSURE INSTALLATION OF GAS LINES ARE COMPLETED PRIOR TO ASPHALT OR CURB PLACEMENT - INSTALL BOLLARD PROTECTION AS SHOWN ON THE PLANS AND PER THE GAS COMPANY REQUIREMENTS	GAS COMPANY RESPONSIBILITY SERVICE FROM THE POINT OF CONNECTION AT THE EXISTING LINE UP TO AND INCLUDING SETTING OF METER WILL BE BY THE GAS COMPANY ANY RELOCATION OF EXISTING WILL BE DONE BY CITY OF ANYTOWN PUBLIC WORKS.	
ELEPHONE: AT&T 34 NW 6TH ST VANSVILLE, IN 47708 PHONE: 812-464-6054 CONTACT: JAMES DANHAUER	COMPANY TO ENSURE INSTALLATION OF UNDERGROUND LINES ARE COMPLETED PRIOR TO ASPHALT OR CURB PLACEMENT - PROVIDE AND INSTALL 2-4" SCHEDULE 40 PVC CONDUITS WITH PULL ROPES, INCLUDING ALL TRENCHING AND BACKFILLING, FROM THE RISER POLE UP TO THE BUILDING - PROVIDE AND INSTALL PULL BOXES AS PER TELEPHONE COMPANY REQUIREMENTS	TELEPHONE COMPANY RESPONSIBILITY TELEPHONE COMPANY WILL PROVIDE AND INSTALL ALL TELEPHONE CABLES FROM THE POINT OF CONNECTION UP TO THE BUILDING ANY RELOCATION OF EXISTING WILL BE DONE BY BELLSOUTH.	
LECTRIC: /ECTREN GAS PO BOX 209 EVANSVILLE, IN 47702 PHONE: 812–491–5010 CONTACT: BRAD VANBIBBER	COMPANY TO ENSURE INSTALLATION OF UNDERGROUND LINES ARE COMPLETED PRIOR TO ASPHALT OR CURB PLACEMENT PROVIDE AND INSTALL 2—4" SCHEDULE 40 PVC CONDUITS WITH PULL ROPES, INCLUDING TRENCHING AND BACKFILLING, FOR THE UNDERGROUND PORTIONS OF THE PRIMARY FROM THE RISER POLE UP TO THE TRANSFORMER. SCHEDULE 80 PVC CONDUITS SHALL BE USED ON THE RISER POLE AND	ELECTRIC COMPANY RESPONSIBILITY - ELECTRIC COMPANY WILL PROVIDE AND INSTALL ALL MATERIALS NEEDED TO ESTABLISH PRIMARY OVERHEAD SERVICE FROM POINT OF CONNECTION AT THE EXISTING LINE UP TO THE TRANSFORMER - ELECTRIC COMPANY WILL PROVIDE AND INSTALL PRIMARY CABLE FOR ALL UNDERGROUND LINES UP TO THE TRANSFORMER - ANY RELOCATION OF EXISTING LINES OR POLES WILL BE DONE BY ELECTRIC COMPANY.	An and and esticated the state of the state
	RIGID METAL, LONG RADIUS, ELBOWS SHALL BE USED WHERE THE UNDERGROUND PORTION MEETS THE RISER POLE		PERMIT CONTACTS
SANITARY SEWER:	AND TRANSFORMER - CONSTRUCT TRANSFORMER PAD AS PER THE ELECTRIC COMPANY'S SPECIFICATIONS - PROVIDE AND INSTALL ALL SECONDARY SERVICE AND MATERIALS - PROVIDE AND INSTALL SANITARY SEWER LINES AND		VANDERBURGH COUNTY 1 NW MARTIN LUTHER KING JR BLVD EVANSVILLE, INDIANA 47708
SANTART SEWER. EVANSVILLE WATER & SEWER UTILITY 1931 ALLENS LN EVANSVILLE, IN 47720 PHONE: 812-421-2120 EXT. 2217 CONTACT: DOUG OHNING	ASSOCIATED APPURTENANCES PER THE PLANS AND SPECIFICATION - ALL PUBLIC AND PRIVATE SANITARY SEWER LINES SHALL BE PVC AND RATED SDR 26 - COORDINATE REQUIRED INSPECTION SERVICES WITH ENGINEER OF RECORD AND EVANSVILLE WATER AND SEWER UTILITY (EWSU). SEE UTILITY PLAN FOR REQUIREMENTS	į	PHONE: 812-435-5117 CONTACT: JEFF MUELLER
WATER: EVANSVILLE WATER & SEWER UTILITY 1931 ALLENS LN EVANSVILLE, IN 47720 PHONE: 812-421-2120 EXT. 2217 CONTACT: DOUG OHNING	- PROVIDE AND INSTALL ALL WATER MAINS AND ASSOCIATED APPURTENANCES PER THE PLANS AND SPECIFICATION - ALL PUBLIC AND PRIVATE WATER MAINS SHALL BE C-900 PVC, DR14 CLASS 200 - ALL PORTIONS OF THE FIRE PROTECTION WATER SYSTEM SHALL BE INSTALLED BY A LICENSED FIRE SPRINKLER CONTRACTOR - ALL PORTIONS OF OTHER NON FIRE PROTECTION RELATED LINES MAY BE INSTALLED BY THE PLUMBING CONTRACTOR - COORDINATE REQUIRED INSPECTION SERVICES WITH ENGINEER OF RECORD AND EVANSVILLE WATER AND SEWER UTILITY (EWSU). SEE UTILITY PLAN FOR REQUIREMENTS.	WATER AGENCY RESPONSIBILITY - DOMESTIC TAP FROM THE POINT OF CONNECTION AT THE EXISTING LINE UP TO AND INCLUDING SETTING OF METER AT THE PROPERTY LINE WILL BE BY THE WATER COMPANY -PRESENT RESPONSIBLE PARTIES - ANY RELOCATION OF EXISTING WILL BE DONE BY CITY OF ANYTOWN PUBLIC WORKSPRESENT RESPONSIBLE PARTIES	No.609 ODAZ
STORM SEWER: COUNTY SURVEYOR (ROOM 325) 1 NW MARTIN LUTHER KING JR BLVD EVANSVILLE, INDIANA 47708 PHONE: 812-435-5117 CONTACT: JEFF MUELLER THIS MATRIX HAS BEE	PROVIDE AND INSTALL ALL STORM SEWER LINES AND ASSOCIATED APPURTENANCES PER THE PLANS AND SPECIFICATION REFER TO GRADING PLAN FOR INFORMATION ON ALLOWABLE STORM SEWER MATERIALS	RECRIVED BY THE VANDERBURGH COUNTY SURVEYOR'S OFFICE	EXP. 7-31-16

Know what's below. Call before you dig.

Within Indiana Call

811 or 800-382-5544

24 Hours a Day, 7 Days a Week.

PER INDIANA STATE LAW IC 8-1-26.

IT IS AGAINST THE LAW TO EXCAVATE WITHOUT NOTIFYING THE UNDERGROUND

LOCATION SERVICE TWO (2) WORKING DAYS BEFORE COMMENCING WORK.

SEE "STATE ROUTE 57 IMPROVEMENTS" AND "E. BOONVILLE/NEW HARMONY ROAD IMPROVEMENTS" (WAL-MART NO. 3374-00)" FOR OFF-SITE HIGHWAY IMPROVEMENTS PREPARED BY MANHARD CONSULTING, LTD

HDWL

INV.

MAX.

FACE TO FACE

FINISHED FLOOR

GRADE AT WALL

FLOW LINE

HEADWAL

HANDHOLE

INVERT

IRON PIPE

MAXIMUM

MAILBOX MEET EXISTING

OPEN LID

FORCE MAIN

FLARED END SECTION

GRADE AT FOUNDATION

GENERAL MERCHANDISE

HIGH WATER LEVEL

NORMAL WATER LEVEL

POINT OF COMPOUND CURVE

PRIVATE ENTRANCE

PROFILE GRADE LINE

POINT OF INTERSECTION PROPERTY LINE

POINT OF CURVE

STANDARD SYMBOLS

DRAINTILE WATER MAIN

STORM MANHOLE CATCH BASIN

VALVE IN BOX

LOW POINT

OVERFLOW RELIEF SWALE

CURB AND GUTTER

REVERSE CURB AND GUTTER

CART CORRAL

EASEMENT LINE SETBACK LINE

TRAFFIC SIGNAL POWER POLE GUY WIRE GAS VALVE HANDHOLE ELECTRICAL EQUIPMENT

TELEPHONE EQUIPMENT CHAIN-LINK FENCE SPOT ELEVATION BRUSH/TREE LINE

DECIDUOUS TREE WITH TRUNK DIA. IN INCHES (TBR)

CONIFEROUS TREE WITH HEIGHT IN FEET (TBR)

RETAINING WALL

WETLAND

EXISTING

 $\sim\sim\sim\sim\sim$

AGGREGATE

BACK TO BACK

BOTTOM OF PIPE

BACK OF WALK

COMMERCIAL ENTRANCE

CORRUGATED METAL PIPE

DUCTILE IRON WATER MAIN

BUFFALO BOX

BITUMINOUS

BENCHMARK

BY OTHERS

CATCH BASIN

CENTERLINE

CLOSED LI

CLEANOU

CONCRETE

DOWNSPOU^{*} DRAIN TILE

ELEVATION

EDGE TO EDGE

EDGE OF PAVEMENT

FIELD ENTRANCE

DUCTILE IRON PIPE

BITUMINOUS AGGREGATE MIXTURE

ARCHITECT

B/P

FOR THE SAFETY OF ANY PARTY AT OR ON THE CONSTRUCTION SITE. SAFETY IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND ANY OTHER PERSON OR ENTITY PERFORMING WORK OR SERVICES. NEITHER THE OWNER NOR ENGINEER ASSUMES ANY RESPONSIBILITY FOR THE JOB SITE SAFETY OF PERSONS ENGAGED IN THE WORK OR THE MEANS OR METHODS OF CONSTRUCTION.

MANHARD CONSULTING, LTD. IS NOT RESPONSIBLE OWNER/DEVELOPER WAL-MART ENTITY

2001 S.E. 10TH STREET BENTONVILLE, ARKANSAS 72716 479-273-4000

POWER POLE

RIGHT-OF-WAY

RAIL ROAD

SANITARY

SHOULDER

STANDARD

SIDEWALK

TO BE REMOVED

TELEPHONE

TOP OF CURB

TOP OF WALK TOP OF WALL

TRANSFORMER

VALVE VAULT WATER LEVEL

WATER MAIN

TEMPORARY

TOP OF FOUNDATION

STREET LIGHT

SANITARY MANHOLE

POINT OF TANGENCY

POLYVINYL CHLORIDE PIPE

POINT OF VERTICAL CURVE


POINT OF VERTICAL INTERSECTION

PUBLIC UTILITY AND DRAINAGE EASEMENT

POINT OF VERTICAL TANGENCY

REINFORCED CONCRETE PIPE

PROPOSED



ROJ. MGR.: TTR

N.T.S. SHEET

11-20-14

GENERAL NOTES

A. PROJECT OFFICE WALL SWPPP POSTINGS:

THE FOLLOWING ITEMS MUST BE POSTED TOGETHER IN A SINGLE, ORGANIZED LOCATION ON A WALL INSIDE THE PROJECT OFFICE: 1) SWPPP SITE MAPS (ALL PHASES); 2) SWPPP DETAIL SHEETS; 3) MAP SHOWING LOCATION OF OFFSITE IMPORT OR EXPORT FACILITY; 4) REVISIONS TO DETAILS, SITE MAPS, OR SWPPP—RELATED RFIS; 5) SITE SWPPP BINDER; 6) SWCT PLACARD; 7) CURRENT OWNER STORMWATER COMPLIANCE TRAINING CERTIFICATES FOR SUPERINTENDENT(S) AND COMPLIANCE OFFICER(S); AND 8) CERTIFICATIONS AND/OR TRAINING CERTIFICATES REQUIRED TO PERFORM INSPECTIONS BY THE APPLICABLE CONSTRUCTION GENERAL PERMIT OR AUTHORITY HAVING JURISDICTION.

B. PERMITTED PROJECT AREA:

FOR PURPOSES OF THIS SWPPP AND ASSOCIATED STORMWATER PERMIT, 'PERMITTED PROJECT AREA' IS DEFINED AS ANY AND ALL AREAS WITHIN THE PROJECT LIMITS OF DISTURBANCE, AS SHOWN ON THE SWPPP SITE MAPS AND IDENTIFIED IN THE NOTICE OF INTENT TO THE AGENCY. ALL GROUND—DISTURBING AND CONSTRUCTION—RELATED ACTIVITIES (MATERIAL STORAGE, DUMPSTERS, PARKING AREAS, PROJECT OFFICE TRAILER, ETC.) MUST BE INCLUDED WITHIN THE PERMITTED PROJECT AREA LIMITS OF DISTURBANCE.

OFFSITE AREA(S) TO BE DISTURBED AS PART OF THIS PROJECT (NOT ON OWNER PROPERTY):

• APPROXIMATELY 850' NORTH AND 650' SOUTH OF THE MAIN DRIVEWAY ENTRANCE ALONG STATE ROUTE 57 IS TO BE WIDENED FOR A SOUTHBOUND RIGHT TURN LANE AND A NORTHBOUND DEDICATED LEFT—TURN LANE.

• APPROXIMATELY 1400' WEST OF THE STATE ROUTE 57 AND E. BOONVILLE/NEW HARMONY ROAD INTERSECTION, E. BOONVILLE/NEW HARMONY ROAD IS TO BE WIDENED FOR AN EASTBOUND LEFT TURN LANE AND A WESTBOUND RIGHT TURN LANE AT THE WAL—MART ACCESS. IN ADDITION, PAVEMENT MARKINGS FOR A LENGTH OF APPROXIMATELY 700' ON THE EAST LEG OF THE INTERSECTION ON BOONVILLE/NEW HARMONY ROAD WILL BE MODIFIED TO ACCOMMODATE FOR AN OPPOSING LEFT TURN ON THIS APPROACH.

• APPROXIMATELY 265' OF STORM SEWER IS BEING INSTALLED ALONG THE NORTH SIDE OF E. BOONVILLE/NEW HARMONY ROAD IMPROVEMENTS, DUE TO WIDENING OF THE ROAD.

APPROXIMATELY 1,215' OF STORM SEWER IS BEING INSTALLED ALONG THE SOUTH SIDE OF E.
BOONVILLE/NEW HARMONY ROAD IMPROVEMENTS, DUE TO WIDENING OF THE ROAD.

• PROPOSED UTILITY CONNECTIONS.

ALL AREAS OUTSIDE THE PERMITTED PROJECT AREA (I.E., LIMITS OF DISTURBANCE) ACQUIRED FOR USE BY THE GC OR A SUBCONTRACTOR OF THE GC (BORROW SOURCES, DISPOSAL AREAS, ETC.) MUST BE MANAGED IN ACCORDANCE WITH APPENDIX E — TAB 21 OF THE 02370 SPECIFICATION. THE CONTRACTOR IS REQUIRED TO LOCATE OFFICE TRAILERS AND MATERIAL STORAGE AREAS FOR THE PROJECT WITHIN THE LIMITS OF DISTURBANCE. THE CONTRACTOR MAY REQUEST USE OF OFF—SITE LOCATIONS FOR OFFICE TRAILERS OR NON—ERODIBLE MATERIAL STORAGE; HOWEVER, APPROVAL MUST BE OBTAINED FROM THE CONSTRUCTION MANAGER, THE CEC AND THE WAL—MART SWCT PRIOR TO THEIR USE. REQUESTS WILL BE REVIEWED ON A CASE BY CASE BASIS AND IF APPROVED, LIMITATIONS ON USE WILL BE PROVIDED BY THE CEC.

C. SPECIAL PROJECT AREAS:

THERE ARE NO SPECIAL PROJECTS, LOCATED BEYOND THE OWNER PERMITTED PROJECT AREA, REQUIRING INSPECTION AND MAINTENANCE ASSOCIATED WITH THIS CONSTRUCTION PROJECT.

D.1 NON-STORMWATER DISCHARGES:

THE GENERAL PERMIT FOR STORMWATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITIES PROHIBITS MOST NON-STORMWATER DISCHARGES DURING THE CONSTRUCTION PHASE. ALLOWABLE NON-STORMWATER DISCHARGES THAT OCCUR DURING CONSTRUCTION ON THIS PROJECT, ARE INCLUDED IN THE SECTION 1.3 OF THE UNITED STATE ENVIRONMENTAL PROTECTION AGENCY (EPA) NPDES GENERAL PERMIT.

BEST MANAGEMENT PRACTICES (BMPS) MUST BE IMPLEMENTED FOR THE GENERAL PERMIT ALLOWABLE DISCHARGES FOR THE DURATION OF THE PERMIT. THE TECHNIQUES DESCRIBED IN THIS SWPPP FOCUS ON PROVIDING CONTROL OF POLLUTANT DISCHARGES WITH PRACTICAL APPROACHES THAT UTILIZE READILY AVAILABLE EXPERTISE, MATERIAL, AND EQUIPMENT.

NON-STORMWATER COMPONENTS OF SITE DISCHARGES MUST BE UNCONTAMINATED NON-TURBID WATER. ALL NON-STORMWATER DISCHARGES MUST BE ROUTED TO A STORMWATER CONTROL PRIOR TO DISCHARGE. WATER USED FOR CONSTRUCTION WHICH DISCHARGES FROM THE SITE MUST ORIGINATE FROM A PUBLIC WATER SUPPLY OR PRIVATE WELL APPROVED BY THE STATE HEALTH DEPARTMENT. WATER USED FOR CONSTRUCTION THAT DOES NOT ORIGINATE FROM AN APPROVED PUBLIC SUPPLY MUST NOT DISCHARGE FROM THE SITE; IT CAN BE RETAINED IN RETENTION PONDS UNTIL IT INFILTRATES OR EVAPORATES. WHEN NON-STORMWATER IS DISCHARGED FROM THE SITE, IT MUST BE DONE IN A MANNER SUCH THAT IT DOES NOT CAUSE EROSION OF THE SOIL DURING

D.2 POWER WASHING:

PROCESS WATER SUCH AS POWER WASHING WATER AND CONCRETE CUTTING EFFLUENT, AMONG OTHERS, MUST BE COLLECTED FOR TREATMENT AND DISPOSAL. IT MUST NOT BE FLUSHED INTO THE SITE STORM DRAIN SYSTEM OR DISCHARGED OFF—SITE.

D. DISCHARGE POINTS:

ALL DISCHARGE POINTS MUST BE INSPECTED TO DETERMINE WHETHER EROSION AND SEDIMENTATION CONTROL MEASURES ARE EFFECTIVE IN PREVENTING DISCHARGE OF SEDIMENT FROM THE SITE AND/OR IMPACTS TO RECEIVING WATERS. SEDIMENT ACCUMULATION DOWNGRADIENT OF DISCHARGE LOCATIONS SHALL BE REPORTED AS A SEDIMENT DISCHARGE (SEE APPENDIX E — TAB 14, SEDIMENT RELEASES, OF THE 02370 SPECIFICATION) AND THE POTENTIAL UPSTREAM CAUSE SHALL BE INVESTIGATED TO PREVENT FUTURE OCCURRENCE. CONTACT THE CM, CEC AND SWCT TO DETERMINE APPROPRIATE ACTION FOR CLEANUP OF DISCHARGED SEDIMENT THAT MAY BE OUTSIDE OF THE LIMITS OF DISTURBANCE. SEE SAMPLING AND MONITORING OF EFFLUENT PLAN (IF APPLICABLE).

EROSION AND SEDIMENT CONTROL NOTES

- A. CONTRACTOR SHALL IMPLEMENT BEST MANAGEMENT PRACTICES AS REQUIRED BY THIS STORM WATER POLLUTION PREVENTION PLAN. ADDITIONAL BEST MANAGEMENT PRACTICES SHALL BE IMPLEMENTED AS DICTATED BY CONDITIONS AT NO ADDITIONAL COST OF OWNER THROUGHOUT ALL PHASES OF CONSTRUCTION.
- B. BEST MANAGEMENT PRACTICES (BMP'S) AND CONTROLS SHALL CONFORM TO FEDERAL, STATE, OR LOCAL REQUIREMENTS OR MANUAL OF PRACTICE, AS APPLICABLE. CONTRACTOR SHALL IMPLEMENT ADDITIONAL CONTROLS AS DIRECTED BY PERMITTING AGENCY OR OWNER.
- C. SITE MAP MUST CLEARLY DELINEATE ALL STATE WATERS. PERMITS FOR ANY CONSTRUCTION ACTIVITY IMPACTING STATE WATERS OR REGULATED WETLANDS MUST BE MAINTAINED ON SITE AT ALL TIMES.
- D. CONTRACTOR TO LIMIT DISTURBANCE OF SITE IN STRICT ACCORDANCE WITH SWPPP IMPLEMENTATION SEQUENCE, OR AS REQUIRED BY THE APPLICABLE GENERAL PERMIT. NO UNNECESSARY OR IMPROPERLY SEQUENCED CLEARING AND/OR GRADING SHALL BE PERMITTED.
- E. ALL DENUDED/BARE AREAS THAT WILL BE INACTIVE FOR 7 DAYS OR MORE, MUST BE STABILIZED IMMEDIATELY UPON COMPLETION OF MOST RECENT GRADING ACTIVITY, WITH THE USE OF FAST-GERMINATING ANNUAL GRASS/GRAIN VARIETIES, STRAW/HAY MULCH, WOOD CELLULOSE FIBERS, TACKIFIERS, NETTING AND/OR BLANKETS. COMPLETION MUST BE ACHIEVED WITHIN 7 DAYS.
- F. DISTURBED PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITY HAS PERMANENTLY STOPPED SHALL BE PERMANENTLY STABILIZED AS SHOWN ON THE PLANS. THESE AREAS SHALL BE SEEDED, SODDED, AND/OR VEGETATED IMMEDIATELY, AND COMPLETED NO LATER THAN 7 DAYS AFTER THE LAST CONSTRUCTION ACTIVITY OCCURRING IN THESE AREAS. REFER TO THE GRADING PLAN AND/OR LANDSCAPE PLAN.
- G. SLOPES SHALL BE LEFT IN A ROUGHENED CONDITION DURING THE GRADING PHASE TO REDUCE RUNOFF VELOCITIES AND EROSION. TEMPORARY AND/OR PERMANENT STABILIZATION SHALL BE APPLIED PER REQUIREMENTS IN THESE E&S CONTROL NOTES.
- H. DUE TO THE GRADE CHANGES DURING THE DEVELOPMENT OF THE PROJECT, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ADJUSTING THE EROSION AND SEDIMENT CONTROL MEASURES (SILT FENCES, ETC.) TO PREVENT EROSION AND POLLUTANT DISCHARGE OFF—SITE.
- I. ALL MEASURES STATED ON THIS SITE MAP, AND IN THE STORM WATER POLLUTION PREVENTION PLAN, SHALL BE MAINTAINED IN FULLY FUNCTIONAL CONDITION UNTIL NO LONGER REQUIRED FOR A COMPLETED PHASE OF WORK OR FINAL STABILIZATION OF THE SITE. ALL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE CHECKED BY A QUALIFIED PERSON IN ACCORDANCE WITH THE CONTRACT DOCUMENTS OR THE APPLICABLE PERMIT, WHICHEVER IS MORE STRINGENT, AND REPAIRED IN ACCORDANCE WITH THE SITE
- J. STORM WATER POLLUTANT CONTROL MEASURES INSTALLED DURING CONSTRUCTION, THAT WILL ALSO PROVIDE STORM WATER MANAGEMENT AFTER CONSTRUCTION, ARE INCLUDED IN THE CONTRACT DOCUMENTS. THE SITE—SPECIFIC POST CONSTRUCTION STORM WATER OPERATION AND MAINTENANCE (O&M) MANUAL IS INCLUDED IN THE CONTRACT DOCUMENTS.
- K. ALL PERMANENT CONTROLS AND SYSTEMS MUST BE INSTALLED AND FUNCTIONING AS DESIGNED AND FREE OF ACCUMULATED SEDIMENT AND DEBRIS DURING FINAL PROJECT INSPECTION AND APPROVAL.

HAZARDOUS MATERIAL MANAGEMENT & SPILL REPORTING

ANY HAZARDOUS OR POTENTIALLY HAZARDOUS MATERIAL THAT IS BROUGHT ONTO THE CONSTRUCTION SITE SHALL BE HANDLED PROPERLY TO REDUCE THE POTENTIAL FOR STORMWATER POLLUTION. ALL MATERIALS USED ON THIS CONSTRUCTION SITE SHALL BE PROPERLY STORED, HANDLED, DISPENSED AND DISPOSED OF FOLLOWING ALL APPLICABLE LABEL DIRECTIONS. FLAMMABLE AND COMBUSTIBLE LIQUIDS SHALL BE STORED AND HANDLED ACCORDING TO APPLICABLE REGULATIONS, AND, AT A MINIMUM, ACCORDING TO 29 CFR 1926.152. ONLY APPROVED CONTAINERS AND PORTABLE TANKS SHALL BE USED FOR STORAGE AND HANDLING OF FLAMMABLE AND COMBUSTIBLE LIQUIDS.

MATERIAL SAFETY DATA SHEETS (MSDS) INFORMATION SHALL BE KEPT ON SITE FOR ANY AND ALL APPLICABLE MATERIALS. HOWEVER, MSDS MAY ALSO BE ACCESSED VIA TELEPHONE OR OTHER ELECTRONIC MEANS OR APPARATUS.

IN THE EVENT OF AN ACCIDENTAL SPILL, IMMEDIATE ACTION SHALL BE TAKEN BY THE GC TO CONTAIN AND REMOVE THE SPILLED MATERIAL. THE SPILL SHALL BE REPORTED TO THE APPROPRIATE AGENCIES IN THE REQUIRED TIME FRAMES. AS REQUIRED UNDER THE PROVISIONS OF THE CLEAN WATER ACT, ANY SPILL OR DISCHARGE ENTERING WATERS OF THE UNITED STATES SHALL BE PROPERLY REPORTED.

ALL HAZARDOUS MATERIALS, INCLUDING CONTAMINATED SOIL AND LIQUID CONCRETE WASTE, SHALL BE DISPOSED OF BY THE CONTRACTOR IN THE MANNER SPECIFIED BY FEDERAL, STATE AND LOCAL REGULATIONS AND BY THE MANUFACTURER OF SUCH PRODUCTS.

THE GC SHALL PREPARE A WRITTEN RECORD OF ANY SPILL AND ASSOCIATED CLEAN—UP ACTIVITIES OF PETROLEUM PRODUCTS OR HAZARDOUS MATERIALS IN EXCESS OF 1 GALLON OR REPORTABLE QUANTITIES, WHICHEVER IS LESS, ON THE DAY OF THE SPILL. THE GC SHALL PROVIDE NOTICE TO OWNER, VIA THE ONLINE CRITICAL INCIDENT REPORT, IMMEDIATELY UPON IDENTIFICATION OF ANY SPILL. SPILL REPORT FORMS ARE AVAILABLE IN THE ONLINE SWPPP REPORTING SYSTEM PROVIDED BY THE OWNER. COPIES OF SPILL CRITICAL INCIDENT REPORTS SHALL BE PRINTED AND MAINTAINED IN THE JOBSITE BINDER.

ANY SPILLS OF PETROLEUM PRODUCTS OR HAZARDOUS MATERIALS IN EXCESS OF REPORTABLE QUANTITIES AS DEFINED BY EPA OR THE STATE OR LOCAL AGENCY REGULATIONS, SHALL BE IMMEDIATELY REPORTED TO THE EPA NATIONAL RESPONSE CENTER (1-800-424-8802) AND the INDIANA DEPARTMENT OF ENVIRONMENTAL MANAGEMENT (1-888-233-7745)

THE STATE REPORTABLE QUANTITY FOR PETROLEUM PRODUCTS IS: 42 GALLONS ANY SPILL THAT EXCEED 55 GALLONS PER 327 IAC 2-6.1-5.

THE REPORTABLE QUANTITY FOR HAZARDOUS MATERIALS CAN BE FOUND IN 40 CFR 302 AND http://gpoaccess.gov/

TO MINIMIZE THE POTENTIAL FOR A SPILL OF PETROLEUM PRODUCT OR HAZARDOUS MATERIALS TO COME IN CONTACT WITH STORMWATER, THE FOLLOWING STEPS SHALL BE IMPLEMENTED:


- 1)ALL MATERIALS WITH HAZARDOUS PROPERTIES, SUCH AS PESTICIDES, PETROLEUM PRODUCTS, FERTILIZERS, SOAPS, DETERGENTS, CONSTRUCTION CHEMICALS, ACIDS, BASES, PAINTS, PAINT SOLVENTS, ADDITIVES FOR SOIL STABILIZATION, CONCRETE, CURING COMPOUNDS AND ADDITIVES, ETC., SHALL BE STORED IN A SECURE LOCATION, UNDER COVER AND IN APPROPRIATE, TIGHTLY SEALED CONTAINERS WHEN NOT IN USE.
- 2) THE MINIMUM PRACTICAL QUANTITY OF ALL SUCH MATERIALS SHALL BE KEPT ON THE JOB SITE AND SCHEDULED FOR DELIVERY AS CLOSE TO TIME OF USE AS PRACTICAL.
- 3) A SPILL CONTROL AND CONTAINMENT KIT (CONTAINING FOR EXAMPLE, ABSORBENT MATERIAL SUCH AS KITTY LITTER OR SAWDUST, ACID, BASE, NEUTRALIZING AGENT, BROOMS, DUST PANS, MOPS, RAGS, GLOVES, GOGGLES, PLASTIC AND METAL TRASH CONTAINERS, ETC.) SHALL BE PROVIDED AT THE CONSTRUCTION SITE AND ITS LOCATION(S) SHALL BE IDENTIFIED WITH LEGIBLE SIGNAGE AND SHOWN ON SITE MAPS.
- a. THE SPILL CONTROL AND CONTAINMENT KIT SUPPLIES SHALL BE OF SUFFICIENT QUANTITIES AND APPROPRIATE CONTENT TO CONTAIN A SPILL FROM THE LARGEST ANTICIPATED PIECE OF EQUIPMENT AND FROM THE LARGEST ANTICIPATED QUANTITIES OF PRODUCTS STORED ON THE SITE AT ANY GIVEN TIME.

 b. CONTENTS SHALL BE INSPECTED DAILY DURING THE DAILY STORMWATER INSPECTION.
- 4) ALL PRODUCTS SHALL BE STORED IN AND USED FROM THE ORIGINAL CONTAINER WITH THE ORIGINAL PRODUCT LABEL. CONTAINERS MUST BE STORED IN A MANNER TO PROTECT THEM FROM THE ELEMENTS AND INCIDENTAL DAMAGE.
- 5) ALL PRODUCTS SHALL BE USED IN STRICT COMPLIANCE WITH INSTRUCTIONS ON THE
- 6) THE DISPOSAL OF EXCESS OR USED PRODUCTS SHALL BE IN STRICT COMPLIANCE WITH INSTRUCTIONS ON THE PRODUCT LABEL AND REGULATIONS.

FLOW ROUTE USGS MAP N.T.S. PROJECT LOCATION

DAYLIGHT QUADRANGLE

VANDERBURGH COUNTY, INDIANA



DEVELOPER/OWNER:
WAL-MART REAL ESTATE BUSINESS TRUST
MAIL STOP 5570
2001 SE 10TH STREET
BENTONVILLE, AR 72716-5570
479-204-1195
SITE OPERATOR/GENERAL CONTRACTOR:

IMPORTANT:
GC MUST SIGN ALL PLAN SHEETS AND ANY NEW
PLAN SHEETS ISSUED BY THE CEC.

SWPPP NOTES

LTING manhard.com ngineers • Wastewater Engineers

CONSULT BOOK PRINGE WATER PROJUCT WATER PROJUCT WATER PROJUCT OF THE PROJUCT OF T

CENTER NO. 3374-00
ITY, INDIANA

ED WAL-MART SUPERCENTE

PROJ. MGR.: TTR

PROJ. MGR.: TTR
PROJ. ASSOC.: BAM
DRAWN BY: MH
DATE: 11-20-14
SCALE: N.T.S.

2 of 37

SHEET

PART OF THE SOUTH HALF OF THE NORTHEAST QUARTER OF SECTION 14, TOWNSHIP 5 SOUTH, RANGE 10 WEST, IN VANDERBURGH COUNTY, INDIANA MORE PARTICULARLY DESCRIBED AS FOLLOWS: COMMENCING AT THE NORTHWEST CORNER OF SAID SOUTH HALF OF THE NORTHEAST QUARTER OF SECTION 14; THENCE SOUTH 88 DEGREES 24 MINUTES 10 SECONDS EAST, 587.60 FEET (BEARINGS BASED ON INDIANA STATE PLANE COORDINATE SYSTEM, WEST ZONE, NAD 1983) ALONG THE NORTH LINE OF SAID SOUTH HALF OF THE NORTHEAST QUARTER TO THE NORTHEAST CORNER OF THE PROPERTY DESCRIBED IN WARRANTY DEED RECORDED MAY 22, 1989 AS INSTRUMENT NO. 1989R00009076 IN THE OFFICE OF THE RECORDER OF VANDERBURGH COUNTY, INDIANA, SAID CORNER ALSO BEING THE POINT OF BEGINNING; THENCE CONTINUING SOUTH 88 DEGREES 24 MINUTES 10 SECONDS EAST, 1285.00 FEET TO THE WEST RIGHT-OF-WAY LINE OF STATE ROUTE 57 AS GRANTED IN DEED RECORD 220, PAGE 281 IN THE OFFICE OF THE RECORDER OF VANDERBURGH COUNTY, INDIANA; THENCE 1231.85 FEET SOUTHWESTERLY ALONG SAID WEST RIGHT-OF-WAY LINE AND THE WEST LINE OF THE PROPERTY CONVEYED TO THE STATE OF INDIANA IN WARRANTY DEED RECORDED AUGUST 10, 2004 AS INSTRUMENT NO. 2004R00027976 IN THE OFFICE OF THE RECORDER OF VANDERBURGH COUNTY, INDIANA, BEING A CURVE CONCAVE TO THE NORTHWEST, HAVING A RADIUS OF 7574.44 FEET, SUBTENDING A CHORD BEARING SOUTH 23 DEGREES 04 MINUTES 37 SECONDS WEST, 1230.49 FEET TO A NON-TANGENT LINE; THENCE SOUTH 27 DEGREES 43 MINUTES 17 SECONDS WEST, 46.22 FEET ALONG LAST SAID WEST LINE; THENCE SOUTH 45 DEGREES 39 MINUTES 32 SECONDS WEST, 92.39 FEET ALONG LAST SAID WEST LINE; THENCE SOUTH 83 DEGREES 56 MINUTES 37 SECONDS WEST, 99.30 FEET ALONG LAST SAID WEST LINE; THENCE SOUTH 65 DEGREES 20 MINUTES 27 SECONDS WEST, 54.06 FEET ALONG LAST SAID WEST LINE TO A LINE 25 FEET NORTH OF AND PARALLEL WITH THE SOUTH LINE OF SAID NORTHEAST QUARTER; THENCE NORTH 88 DEGREES 24 MINUTES 31 SECONDS WEST, 599.38 FEET ALONG SAID PARALLEL LINE TO THE EAST LINE OF THE PROPERTY DESCRIBED IN WARRANTY DEED RECORDED AUGUST 6, 1991 AS INSTRUMENT NO. 1991R00018072 IN THE OFFICE OF THE RECORDER OF VANDERBURGH COUNTY, INDIANA; THENCE NORTH 01 DEGREES 26 MINUTES 21 SECONDS EAST, 1290.13 FEET ALONG LAST SAID EAST LINE AND THE EAST LINE OF THE PROPERTY DESCRIBED IN WARRANTY DEED RECORDED SEPTEMBER 10, 2009 AS INSTRUMENT NO. 2009R00024363 IN THE OFFICE OF THE RECORDER OF VANDERBURGH COUNTY, INDIANA, AND THE EAST LINE OF THE PROPERTY DESCRIBED IN SAID WARRANTY DEED RECORDED AS INSTRUMENT NO. 1989R00009076 TO THE POINT OF BEGINNING.

, 1.	· · · · · · · · · · · · · · · · · · ·	SEE SHEETS 12-27 05140202040050
	14 DIGIT TITDICOLOGIO CITIT COSE	NONE REQUIRED
	STORMWATER DISCHARGE POINTS	SEE SHEET 19. ALL STORMS UP TO AND INCLUDING THE 100 YEAR EVENT ARE TO BE DETAINED WITHIN THE PROPOSED ON—SITE STORMWATER DETENTION POND AND RELEASED AT A CONTROLLED RATE THROUGH A RESTRICTOR STRUCTURE AND DIRECTED TOW SCHLENSKER DITCH. A PROPOSED EMERGENCY OVERFLOW WEIRD IS PROPOSED TO DIRECT ANY EMERGENCY OVERFLOW TOWARDS SCHLENSKER DITCH.
0 1	-	SEE SHEET 2. THE NEAREST WATER COURSE TO THE SITE IS SCHLENSKER DITCH, AND IS LOCATED AT THE NORTHERN PORTION THE SITE.
	<u> </u>	SEE SHEET 2. THE NEAREST RECEIVING WATER FOR THE SITE IS SCHLENSKER DITCH LOCATED 0.00 MILES TO THE NORTH OF THE SITE.
2	CROUND WATER	THE PROPOSED STORMWATER DETENTION POND IS A POTENTIAL DISCHARGE TO GROUNDWATER
	FLOOD FRINGES	SEE SHEET 4 & 5. THE SITE IS LOCATED WITHIN A ZONE AE DESIGNATION WITH A BASE FLOOD ELEVATION OF 394.0 ACCORDING THE FEMA FLOOD INSURANCE RATE MAP (FIRM) PANEL MAP NUMBER 18163CO128D WITH AN EFFECTIVE DATE OF MARCH 17, 201
4	EST OF DEAK DISCHARGE	SEE STORM WATER MANAGEMENT REPORT. PRE—CONSTRUCTION PEAK DISCHARGE (10—YEAR) = 13.62 CFS AND POST CONSTRUC PEAK DISCHARGE (25—YEAR) = 10.05 CFS, PEAK DISCHARGE (100—YEAR) = 11.36 CFS.
	7,000	ADJACENT LAND NORTH OF THE SITE CONTAINS CROP FIELDS. ADJACENT LAND EAST OF THE SITE CONTAINS CROP FIELDS. ADJACENT LAND WEST OF THE SITE CONTAINS CROP FIELDS AND RESIDENTIAL USE. ADJACENT LAND SOUTH OF THE SITE IS RESIDENTIAL. ADJACENT LAND SOUTHEAST OF THE SITE IS GENERAL INDUSTRIAL USE.
6	LOCATIONS AND APPROXIMATE BOUNDARIES OF ALL DISTURBED AREAS	SEE SHEET 4, 5, & 19 FOR BOUNDARIES OF ALL DISTURBED LANDS.
7	IDENTIFICATION OF EX VEGETATION COVER	SEE SHEET 12 FOR EXISTING VEGETATION COVER.
	130123 MIAI INOCODINO DECONII NONO ANTE	SEE SHEET 4 & 6 OF THE PLAN SET AND THE GEOTECHNICAL REPORT DATED JUNE 16TH, 2014. SOILS PRESENT INCLUDE LOWE STRENGTH LEAN CLAY SOILS AND SILTY CLAY SOILS WITH RELATIVELY HIGH MOISTURE CONTENTS BELOW TOPSOIL. IN SOME INSTANCE, SANDY LEAN CLAY (CL) AND CLAYEY SAND (SC) WERE FOUND BELOW THE LEAN CLAY (CL), BUT GENERALLY BORING TERMINATED WITH LEAN CLAY (CL). LEAN CLAY (CL) DESCRIPTION — FINE GRAINED, INORGANIC CLAY OF LOW PLASTICITY LIMITATION — POORLY DRAINED, PRACTICALLY IMPERVIOUS CLAYEY SAND (SC) DESCRIPTION — COURSE GRAINED, SAND WITH >12% FINES. HIGH STRENGTH UNDER LOADS. LIMITATION — LOW PLASTICITY AND COMPRESSIBILITY.
	O CONTRACTOR OF	SEE SHEET 19
	LOOATION SIZE & BIMO STOTEMENT DE STOTEMENT	SEE SHEET 13
	OFF-SITE CONSTRUCTION ACTIVITIES	SEE SHEET 4
	LOCATION OF PROPOSED SOIL STOCKPILES EXISTING SITE TOPOGRAPHY	SEE SHEET 12
	PROPOSED FINAL TOPOGRAPHY	SEE SHEET 16
	DESCRIPTION OF POTENTIAL POLLUTANT SOURCES	
	ASSOCIATED WITH CONSTRUCTION	
2	SEQUENCE DESCRIBING STORM WATER QUALITY MEASURE IMPLEMENTATION	SEE SHEETS 3-9.
 3	CONSTRUCTION ENTRANCE LOC AND SPEC	SEE SHEETS 4, 5 & 7
 4	SEDIMENT CONTROL FOR SHEET FLOW AREAS	SEE SHEETS 4, 5 & 7-8
 5	SEDIMENT CONTROL CONCENTRATED FLOW	SEE SHEETS 4, 5 & 7-8
— 6	STORM SEWER INLET PROTECTION MEASURES	SEE SHEETS 4, 5, 7 & 8
7	RUNOFF CONTROL MEASURES	SEE SHEETS 4, 5, 7 & 8
8	STORM WATER OUTLET PROTECTION SPECS	RIP-RAP IS USED FOR ALL THE STORMWATER OUTLETS.
	GRADE STABILIZATION LOC AND SPECS	SEE SHEETS 4-9 FOR ALL BMPS AND ASSOCIATED DETAILS USED ON THE SITE FOR GRADE STABILIZATION.
10	LOCATION DIM SPECS AND CONST DETAILS OF EACH STORMWATER QUALITY MEASURE	SEE SHEETS 4-9
	TEMP SURFACE STABILIZATION METHODS	SEE SHEETS 3-9
	PERMANENT SURFACE STABILIZATION SPECS	SEE SHEETS 5-9, & 13
	MATERIAL HANDLING AND SPILL PREVENTION	SEE SHEET 2
	MONITORING AND MAINTENANCE FOR EACH PROPOSED POLLUTION PREVENTION MEASURE	SEE SHEETS 2-9
15	EROSION & SEDIMENT CONTROL SPECS FOR INDIVIDUAL BUILDING LOTS	SEE SHEETS 2-9
:1	DESCRIPTION OF POLLUTANTS AND THEIR SOURCES ASSOCIATED WITH LAND USE	POTENTIAL POLLUTANT SOURCES FOR THE PROPOSED LAND USE ARE OIL, GREASE, ANTIFREEZE, BRAKE FLUID AND BRAKE DUS RUBBER FRAGMENTS, GASOLINE, DIESEL FUEL AND OTHER HYDROCARBONS AND METALS FROM VEHICULAR AND OTHER SOURCES TRASH (INCLUDING BACTERIA AND OTHER BIOLOGICAL AGENTS CONTAINED IN THE TRASH) FROM LITTERING AND OTHER TYPES IMPROPER DISPOSAL OR STORAGE.
2	IN ADLIENCHTATION	SEE SHEETS 3-9. SEQUENCE DESCRIBING STORMWATER QUALITY MEASURE IMPLEMENTATION CAN BE FOUND ON THIS PLAN, TO THE RIGHT OF THIS TABLE.
3	DESCRIPTION OF PROPOSED POST CONSTRUCTION STORM WQ MEASURES	SEE SHEETS 3-9. THE POST CONSTRUCTION STORMWATER QUALITY MEASURE FOR THE SITE IS THE PROPOSED DETENTION PON ALL POST CONSTRUCTION POLLUTANTS WILL REMAIN AT THE BOTTOM OF THE POND UNTIL REMOVED DURING SCHEDULED POND MAINTENANCE.
	THE PER PER AND CONCE DETAILS OF	
C4	LOCATION DIM SPEC AND CONST DETAILS OF EACH STORMWATER QUALITY MEASURE	SEE SHEETS 4-9. REFER TO OPERATION AND MAINTENANCE MANUAL, SPECIFICATION SECTION 02370, APPENDIX C, FOR THE REQUIRED MAINTENANCE GUIDELINE

SWPPP IMPLEMENTATION SEQUENCE

NOTE: UPON IMPLEMENTATION AND INSTALLATION OF THE FOLLOWING AREAS: TRAILER, PARKING, LAY DOWN, PORTA-POTTY, WHEEL WASH, CONCRETE WASHOUT, MASON'S AREA, FUEL AND MATERIAL STORAGE AREAS/CONTAINERS, SOLID WASTE CONTAINERS, ETC., IMMEDIATELY DENOTE THEM ON THE SITE MAPS AND NOTE ANY CHANGES IN LOCATION AS THEY OCCUR THROUGHOUT THE CONSTRUCTION PROCESS. IN ADDITION, NOTE ALL AREAS WHERE FILL IS IMPORTED FROM OR SOIL IS EXPORTED TO ON THE SITE MAPS.

NOTE: DOWN SLOPE PROTECTIVE MEASURES MUST ALWAYS BE IN PLACE BEFORE SOIL IS DISTURBED. ACTIVITIES ARE PRESENT IN THE ORDER OR SEQUENCE IN WHICH THEY ARE REQUIRED TO BE COMPLETED.

- 1. INSTALL THE SWPPP INFORMATION SIGN AND POST REQUIRED DOCUMENTS NEAR THE PLANNED CONSTRUCTION EXIT, AND WITHIN EASY ACCESS TO THE GENERAL PUBLIC WITHOUT ENTERING THE SITE.
- 2. STAKE/FLAG THE LOD (WHERE STAKING IS NOT POSSIBLE/PRACTICAL, THE LOD MUST BE CONSPICUOUSLY, AND PROMINENTLY, MARKED TO DENOTE THE BOUNDARY). LOD MUST REMAIN CONSPICUOUSLY MARKED THROUGHOUT
- THE ENTIRE CONSTRUCTION PROJECT. 3. INSTALL INLET PROTECTION AND CULVERT INLET PROTECTION IN EXISTING STORM STRUCTURES IN THE LIMITS OF
- 4. INSTALL PERIMETER SEDIMENT CONTROL BMPS IN THE VICINITY OF, AND DOWN GRADIENT FROM, THE LOCATION OF THE PLANNED CONSTRUCTION EXIT, CONSTRUCTION OFFICE TRAILER, AND TEMPORARY PARKING AND STORAGE AREAS. CLEAR ONLY THE MINIMUM AREA ABSOLUTELY NECESSARY TO INSTALL THESE PERIMETER CONTROL BMPS.
- 5. INSTALL STABILIZED CONSTRUCTION EXIT(S) WITH SEDIMENT TRAPS, AND SET THE PROJECT OFFICE TRAILER. 6. INSTALL REMAINING PERIMETER SEDIMENT CONTROL BMPS, AS SHOWN ON THE SITE MAPS. CLEAR ONLY THE MINIMUM AREA NECESSARY TO INSTALL PERIMETER CONTROL BMPS.
- 7. PREPARE TEMPORARY PARKING AND STORAGE AREA. INSTALL ONSITE RAIN GAUGE.
- 8. HALT ALL ACTIVITIES

CONTACT THE CEC TO PERFORM INSPECTION AND CERTIFICATION OF BMPS. BMP CERTIFICATION MUST OCCUR BEFORE STORMWATER PRE-CONSTRUCTION MEETING. (THIS SHOULD BE SCHEDULED IN ADVANCE, IN ANTICIPATION OF THE EXPECTED DATE WHEN THE ABOVE SEQUENCE ITEMS WILL BE COMPLETED.)

ALL EXCEPTIONS NOTED ON THE BMP CERTIFICATION FORM MUST BE ADDED AS DEFICIENCIES WITHIN THE BMP CERTIFICATION FORM AND RESOLVED WITHIN 24-HOURS. BMPS MUST NOT BE CERTIFIED IF ONE OR MORE OF THE EXCEPTIONS WILL NOT BE RESOLVED WITHIN 24-HOURS OF THE BMP CERTIFICATION BY THE CEC.

IF THE CEC IS UNABLE TO CERTIFY THAT SITE CONDITIONS ARE PER PLANS AND SPECIFICATIONS, THE CERTIFICATION OF BMPS MUST BE RESCHEDULED. THE STORMWATER PRE-CONSTRUCTION MEETING MAY ONLY OCCUR AFTER BMPS CAN BE

GENERAL CONTRACTOR SHALL SCHEDULE AND CONDUCT THE STORMWATER PRE-CONSTRUCTION MEETING WITH THE CEC, OWNER'S CONSTRUCTION MANAGER, AGENCY(IES) AND SUBCONTRACTORS BEFORE PROCEEDING WITH

DAILY STORMWATER INSPECTION REPORTS IN THE ONLINE SWPPP REPORTING SYSTEM PROVIDED BY THE OWNER MUST START ON THE NEXT BUSINESS DAY AFTER THE SITE BMPS & PRECONSTRUCTION MEETING CERTIFICATION IS SIGNED/CERTIFIED BY THE CEC.

- 9. CLEAR, GRUB, AND STRIP ONLY THE MINIMUM AREA ABSOLUTELY NECESSARY TO INSTALL SEDIMENT BASIN, INCLUDING STOCKPILE AREAS NECESSARY FOR SPOIL FROM THESE REQUIRED STRUCTURAL SEDIMENT CONTROL
- 10. CONSTRUCT SEDIMENT BASIN WITH TEMPORARY PERFORATED RISER AND OUTLET PIPE, AS SPECIFIED ON THE SITE
- 11. STABILIZE SIDE SLOPES AND ALL SIDES OF EMBANKMENTS OR SLOPES OF SEDIMENT BASIN IMMEDIATELY UPON COMPLETION, AS SPECIFIED IN THE SWPPP.
- 12. INSTALL HYDRAULIC CONTROL STRUCTURES (DIVERSION DIKES, DIVERSION CHANNELS, CHECK DAMS, ETC.), AS
- SPECIFIED ON THE SITE MAPS. 13. STABILIZE SIDE SLOPES AND FLOW LINE OF HYDRAULIC CONTROL STRUCTURES (DIVERSION DIKES AND DIVERSION CHANNELS) WITH SEED, FERTILIZER AND ROLLED EROSION CONTROL BLANKETS, AS SPECIFIED IN THE SWPPP.

BEGIN CLEARING, GRUBBING, AND STRIPPING THE SITE. (PHASE CLEARING AND GRUBBING TO THE EXTENT PRACTICAL TO

- MINIMIZE THE AMOUNT OF AREA DISTURBED AT ANY POINT IN TIME)
- BEGIN GRADING THE SITE. START CONSTRUCTION OF BUILDING PAD AND STRUCTURES.
- 4. TEMPORARILY STABILIZE, THROUGHOUT CONSTRUCTION IMMEDIATELY FOLLOWING THE COMPLETION OF THE MOST RECENT LAND DISTURBING/GRADING ACTIVITY, ANY DISTURBED AREAS, INCLUDING MATERIAL STOCKPILES THAT ARE SCHEDULED OR LIKELY TO REMAIN INACTIVE FOR 14 DAYS OR MORE.
- 5. IMMEDIATELY PERMANENTLY STABILIZE AREAS TO BE VEGETATED AS THEY ARE BROUGHT TO FINAL GRADE.
- INSTALL UTILITIES, UNDERDRAINS, STORM SEWERS, CURBS AND GUTTERS.
- 7. INSTALL RIP RAP AROUND OUTLET STRUCTURES AS EACH OUTLET STRUCTURE IS INSTALLED. 8. INSTALL INLET PROTECTION AT ALL STORM SEWER STRUCTURES AS EACH INLET STRUCTURE IS INSTALLED.
- 9. PREPARE SITE FOR PAVING.
- 10. PAVE SITE. 11. INSTALL APPROPRIATE INLET PROTECTION DEVICES FOR PAVED AREAS AS WORK PROGRESSES, PER BMP DETAILS.
- 12. COMPLETE GRADING AND INSTALLATION OF PERMANENT STABILIZATION OVER ALL AREAS, INCLUDING OUT LOTS AND PONDS. SEDIMENT ACCUMULATED WITHIN THE TEMPORARY SEDIMENT BASIN TO BE REMOVED AND DISPOSED OF ACCORDING TO STATE AND FEDERAL STANDARDS.
- 13. OBTAIN CONCURRENCE FROM THE OWNER CONSTRUCTION MANAGER (CM) THAT THE SITE HAS BEEN FULLY STABILIZED AND ALL CONSTRUCTION HAS BEEN COMPLETED, THEN:
- A. REMOVE ALL REMAINING TEMPORARY EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICES (BMPS), B. STABILIZE ANY AREAS DISTURBED BY THE REMOVAL OF TEMPORARY BMPS, AND
- C. ASK THE CM TO CONTACT THE CEC TO COMPLETE THE CEC PRE-NOT SITE INSPECTION AND REPORT (ONLY CM MAY DO
- 14. CONTINUE DAILY INSPECTIONS AND REPORTS UNTIL THE CM FINAL DAILY INSPECTION REPORT, MARKED 'READY TO TERMINATE PERMIT, IS SIGNED BY THE CONSTRUCTION MANAGER AND SUBMITTED VIA THE ONLINE SWPPP REPORTING SYSTEM PROVIDED BY THE OWNER.

NOTE: THE GENERAL CONTRACTOR MAY COMPLETE CONSTRUCTION-RELATED ACTIVITIES CONCURRENTLY, ONLY IF ALL PRECEDING BMPS AND STABILIZATION ACTIVITIES HAVE BEEN COMPLETELY INSTALLED. BMP-RELATED STEPS IN THE ABOVE SEQUENCE ARE BOLDED FOR CLARITY. THE CEC MUST APPROVE, IN WRITING, ANY CHANGES IN THE ABOVE SWPPP IMPLEMENTATION SEQUENCE, BEFORE THEIR IMPLEMENTATION BEGINS.

THE ESTIMATED DATES OF IMPLEMENTATION OF POLLUTION CONTROL MEASURES SHALL BE DOCUMENTED BY THE CONTRACTOR ON THE SOIL EROSION/SEDIMENATION CONTROL OPERATION TIME SCHEDULE ON SHEET 9.

MINIMIZATION OF DISTURBED AREAS:

- 1. CONTRACTOR SHALL MANAGE CONSTRUCTION ACTIVITIES TO REDUCE EROSION AND RETAIN SEDIMENT AND OTHER POLLUTANTS IN THE SOIL AT THE CONSTRUCTION SITE.
- 2. CONTRACTOR SHALL MINIMIZE THE TIME BARE SOIL IS EXPOSED.
- 3. CONTRACTOR SHALL MINIMIZE SITE DISTURBANCE BY MINIMIZING THE EXTENT OF GRADING AND CLEARING TO EFFECTIVELY REDUCE SEDIMENT YIELD.

NOTE TO GC: OWNER HAS AUTHORITY AT ANY TIME TO LIMIT SURFACE AREA OF ERODIBLE EARTH MATERIAL EXPOSED BY CLEARING AND GRUBBING, EXCAVATION, BORROW AND EMBANKMENT OPERATIONS AND TO DIRECT THE GC TO PROVIDE IMMEDIATE PERMANENT OR TEMPORARY POLLUTION CONTROL MEASURES.


DEVELOPER/OWNER: WAL-MART REAL ESTATE BUSINESS TRUST MAIL STOP 5570 2001 SE 10TH STREET BENTONVILLE, AR 72716-5570 479-204-1195 SITE OPERATOR/GENERAL CONTRACTOR:


SUPERINTENDENT:

GC MUST SIGN ALL PLAN SHEETS AND ANY NEW PLAN SHEETS ISSUED BY THE CEC.

PROJ. MGR.: TTR PROJ. ASSOC.: BAM 11-20-14 N.T.S. SCALE:

SHEET





- SUBSTANCES THAT HAVE THE POTENTIAL FOR POLLUTING SURFACE AND/OR GROUNDWATER MUST BE CONTROLLED BY ANY MEANS NECESSARY TO ENSURE THAT THOSE DO NOT DISCHARGE FROM THE SITE. IN THIS REGARD, POTENTIALLY POLLUTING SUBSTANCES SHALL BE STORED AND HANDLED IN A MANNER CONSISTENT WITH THE RISK OF IMPACT THOSE REPRESENT, AND ACCORDING WITH THE REGULATIONS.
- NO SOLID MATERIALS, INCLUDING BUILDING MATERIALS, ARE ALLOWED TO BE DISCHARGED FROM THE SITE WITH STORMWATER. ALL SOLID WASTE, INCLUDING DISPOSABLE MATERIALS INCIDENTAL TO THE CONSTRUCTION ACTIVITIES, MUST BE COLLECTED AND PLACED IN CONTAINERS. RUBBISH, TRASH, GARBAGE, LITTER, OR OTHER SUCH MATERIALS SHALL BE DEPOSITED INTO SEALED CONTAINERS. MATERIALS SHALL BE PREVENTED FROM LEAVING THE PREMISES THROUGH THE ACTION OF WIND OR STORMWATER DISCHARGE INTO DRAINAGE DITCHES OR WATERS OF THE STATE. THE CONTAINERS SHALL BE HAULED AWAY FROM THE SITE AND EMPTIED WHEN THOSE BECOME 95% FULL, OR AS NECESSARY, BY A CERTIFIED TRASH DISPOSAL SERVICE. LIDS OR COVERS FOR THE CONTAINERS SHALL BE PROVIDED FOR USE DURING RAIN EVENTS TO PREVENT WASTE CONTACT WITH STORMWATER. WASTES THAT CANNOT BE STORED IN A CONTAINER MUST BE STORED UNDER COVER OR INDOORS. THE LOCATION OF SOLID WASTE RECEPTACLES SHALL BE SHOWN ON THE SITE



|WAL-MART STANDARD DETAIL LAST REVISED: JUNE 2013

NOTES:

- CONTRACTOR SHALL PROVIDE DESIGNATED LOCATION FOR SORTING AND SEPARATING HAZARDOUS WASTES.
- HAZARDOUS WASTE STORAGE MUST BE PROTECTED FROM WEATHER ELEMENTS AND HAVE RESTRICTED
- HAZARDOUS WASTE STORAGE MUST COMPLY WITH LOCAL, STATE, AND FEDERAL REGULATIONS.
- HAZARDOUS WASTE STORAGE MUST COMPLY WITH CONTRACT DOCUMENTS.

(11147)	HAZARDOUS	WASTE	DISPOSAL
HWD			

WAL-MART STANDARD DETAIL LAST REVISED: JUNE 2013

ALL PERSONNEL INVOLVED WITH CONSTRUCTION ACTIVITIES MUST COMPLY WITH STATE AND LOCAL SANITARY OR SEPTIC SYSTEM REGULATIONS. PORTABLE TOILETS MUST BE LOCATED AT LEAST 30 FEET FROM INLETS, CHANNELS, SWALES, OR PERMITTED LIMITS OF DISTURBANCE, AND MUST BE LOCATED AT LEAST 50 FEET FROM WATERS OF THE STATE, OR WATERS OF THE U.S.. PORTABLE TOILETS MUST BE SECURELY ANCHORED AND/OR TIED DOWN. SECONDARY CONTAINMENT SHALL BE PROVIDED AND FULL CAPACITY SHALL BE RESTORED IMMEDIATELY UPON DISCOVERY OF ITS DIMINISHMENT. THE LOCATION OF SANITARY FACILITIES SHALL BE SHOWN ON THE SITE MAPS.



WAL-MART STANDARD DETAIL LAST REVISED: JUNE 2013

NOTES:

THE TEMPORARY PARKING AND STORAGE AREA SHALL BE KEPT IN GOOD CONDITION (SUITABLE FOR PARKING AND STORAGE). THIS MAY REQUIRE PERIODIC TOP DRESSING OF THE TEMPORARY PARKING AREA AS CONDITIONS DEMAND.



WAL-MART STANDARD DETAIL LAST REVISED: JUNE 2013

NOTES:

- STORM DRAIN INLET PROTECTION MEASURES SHALL PREVENT SOIL AND DEBRIS FROM ENTERING STORM
- 2. TEMPORARY CONTROLS SHALL BE CONSTRUCTED BEFORE THE SURROUNDING AREA IS DISTURBED. TO PREVENT CLOGGING, STORM DRAIN CONTROL STRUCTURES MUST BE MAINTAINED FREQUENTLY.
- 4. CHECK ALL TEMPORARY CONTROL MEASURES DAILY, AND AFTER EACH STORM EVENT.
- CONTROL MEASURES MUST BE BUILT PER DETAIL AND PLANS, AND MUST BE IN GOOD WORKING



WAL-MART STANDARD DETAIL LAST REVISED: JUNE 2013

CONDITION AT ALL TIMES.

- VERIFY WITH CEC WHICH DISCHARGES FROM DEWATERING ACTIVITIES ARE ALLOWED OR ARE NOT ALLOWED NON-STORMWATER DISCHARGES UNDER THE GENERAL PERMIT AND OTHER REGULATIONS. OBTAIN ALL DEWATERING PERMITS AND AUTHORIZATIONS REQUIRED BY STATE AND LOCAL REGULATIONS. SEE THE REQUIRED DEWATERING PERMITS AND AUTHORIZATIONS TABLE BELOW. GC MUST COMPLETE COLUMNS 3 AND 4.
- 2. GC MUST WAIT TO HAVE WRITTEN COPY OF ALL REQUIRED DEWATERING PERMITS AND AUTHORIZATIONS BEFORE PERFORMING DEWATERING ACTIVITIES.
- 3. DISCHARGES FROM DEWATERING OPERATIONS MUST BE DIRECTED THROUGH AN APPROPRIATE POLLUTION PREVENTION/TREATMENT SYSTEM OF CONTROL MEASURES, SUCH AS A SEDIMENT/FILTER BAG, SEDIMENT TRAP OR SEDIMENT BASIN, AND OTHERS, AS NEEDED, PRIOR TO BEING DISCHARGED FROM THE SITE OR INTO A WATER BODY OF THE STATE. UNDER NO CIRCUMSTANCES ARE DISCHARGES FROM DEWATERING OPERATIONS TO BE DISCHARGED DIRECTLY INTO SANITARY SEWER SYSTEMS, STREAMS, RIVERS, LAKES OR OTHER AREAS BEYOND THE PERMITTED PROJECT AREA. LIKEWISE, DISCHARGES INTO STORM SEWER SYSTEMS THAT DO NOT DRAIN TO A SUITABLE ON-SITE TREATMENT FACILITY, SUCH AS A BASIN, ARE ALSO PROHIBITED. DISCHARGES FROM DEWATERING OPERATIONS MUST ALSO BE CONDUCTED IN A MANNER SUFFICIENT TO PREVENT EROSION FROM THE
- IN SEDIMENT TRAP OR BASIN OR POND DEWATERING OPERATIONS, WATER MUST ONLY BE REMOVED FROM THE SURFACE OF THE CONTAINED WATER. A SKIMMER OR SIMILAR FLOATING DEVICE MUST BE USED. TO ONLY REMOVE THE WATER AT THE SURFACE.
- 5. DO NOT DISCHARGE ON A SLOPE GREATER THAN THREE PERCENT NOR WITHIN 20 FEET OF A SURFACE WATER
- 6. DEWATERING SHALL NOT OCCUR DURING OR IMMEDIATELY AFTER PRECIPITATION EVENTS, BUT EXCEPTIONS SHALL BE EVALUATED ON CASE BY CASE BASIS. CONTACT THE CEC AND RECEIVE WRITTEN APPROVAL.

REQUIR	ED DEWATERING PERM	ITS AND AUTHORIZATI	ONS
1	2	3	4
GOVERNING AGENCY	PERMIT NAME/TYPE	PERMIT NO. (GC TO COMPLETE)	DATE PERMIT WAS ISSUED BY AGENCY (GC TO COMPLETE)
COUNTY OF VANDERBURGH	DEWATERING PERMIT		

MATERIAL STORAGE AREAS SHOULD BE LOCATED, WHEN POSSIBLE, TO MINIMIZE EXPOSURE TO WEATHER.

INSPECTIONS SHALL EVALUATE DISTURBED AREAS AND AREAS USED FOR STORING MATERIALS THAT ARE

EXPOSED TO RAINFALL FOR EVIDENCE OF, OR THE POTENTIAL FOR, POLLUTANTS ENTERING THE DRAINAGE

SYSTEM OR DISCHARGING FROM THE SITE. IF NECESSARY, THE MATERIALS MUST BE COVERED OR ORIGINAL

COVERS MUST BE REPAIRED OR SUPPLEMENTED. ALSO, PROTECTIVE BERMS MUST BE CONSTRUCTED, IF NEEDED. TO CONTAIN RUNOFF FROM MATERIAL STORAGE AREAS. GC SHALL ADHERE TO ALL STATE AND

CHEMICALS, PAINTS, SOLVENTS, FERTILIZERS, AND OTHER TOXIC MATERIALS MUST BE STORED IN WATERPROOF

CONTAINERS. EXCEPT DURING APPLICATION, THE CONTAINERS AND THE CONTENTS MUST BE KEPT IN TRUCKS

OR INSIDE OF STORAGE FACILITIES. RUNOFF CONTAINING SUCH MATERIAL MUST BE COLLECTED. REMOVED

FROM THE SITE, TREATED, AND DISPOSED OF AT AN APPROVED SOLID WASTE AND CHEMICAL DISPOSAL

MATERIAL LAYDOWN

CONCRETE WASTE MANAGEMENT PERTAINS TO WASTE FROM CONCRETE READY-MIX TRUCKS, MASONRY

STATE AND LOCAL REGULATIONS DO NOT PROHIBIT IN-GROUND CONCRETE WASHOUT PITS ON-SITE. RULE 5

AREAS WHÈRE CONCRETE TRUCK WASHOUT IS PERMISSIBLE TO BE CLEARLY POSTED AT APPROPRIATE AREAS

SECTION 7(B)(2) OF THE INDIANA NPDES GENERAL PERMIT RULE PROGRAM REQUIRES IDENTIFICATION OF

DISCHARGE OF EXCESS OR WASTE CONCRETE AND/OR WASH WATER FROM CONCRETE TRUCKS IS ALLOWED

IDENTIFIED BY LEGIBLE SIGNAGE, AND MUST BE LOCATED OUTSIDE OF VEGETATED BUFFERS AND AS FAR AS

COMPONENTS OF THE MIX. CONCRETE WASHOUT CONTAINERS MUST BE CLEANED OR EXCHANGED WHEN THE

AT THE CONSTRUCTION SITE. ONLY COMMERCIALLY AVAILABLE ABOVE GROUND PORTABLE CONCRETE

WASHOUT CONTAINERS ARE ALLOWED AND MUST BE PROTECTED FROM VEHICLE TRAFFIC AND CLEARLY

PRACTICABLE FROM STORMWATER CONVEYANCES AND IMPOUNDMENTS AND WATER BODIES. PORTABLE

CONCRETE WASHOUT CONTAINERS SHALL CONTAIN AND/OR ACTIVELY MANAGE BOTH, SOLID AND FLUID.

REMAINING VOLUME IS REDUCED BY 85% TO PREVENT ANY POTENTIAL OVERFLOW IN A STORM EVENT.

OF CONCRETE WASHOUT CONTAINERS SHALL BE SHOWN ON THE SITE MAPS.

PROVIDE WASH STATION IN A LOCATION PROTECTED FROM WEATHER ELEMENTS.

2. COLLECT ALL USED WASH WATER AND DISPOSE OF IT PROPERLY

ALTERNATIVELY, WASTE CONCRETE CAN BE PLACED INTO FORMS TO MAKE RIP RAP AND/OR OTHER USEFUL

CONCRETE PRODUCTS. PORTABLE CONCRETE WASHOUT CONTAINERS SHALL BE DISPOSED IN ACCORDANCE

3. PROVIDE ADEQUATE SUPPLY OF WATER AND ANY OTHER SUPPLIES TO ENSURE PROPER OPERATION OF WASH

PAINT AND STUCCO WASHOUT

WITH APPLICABLE LOCAL, STATE AND FEDERAL REGULATIONS. THE GC IS RESPONSIBLE FOR ASSURING THAT

THESE PROCEDURES, APPLICABLE LAWS, AND ENVIRONMENTAL REGULATIONS ARE FOLLOWED. THE LOCATION

CEMENT AND CONCRETE WASHOUT

AND STORAGE AREA

WAL-MART STANDARD DETAIL LAST REVISED: JUNE 2012

WAL-MART STANDARD DETAIL

LAST REVISED: JUNE 2013

OPERATIONS, AND SIMILAR WASTE.

WAL-MART STANDARD DETAIL

LAST REVISED: JUNE 2013

STATION WHEN NEEDED.

WAL-MART STANDARD DETAIL

LAST REVISED: JUNE 2013

NOTES:

LOCAL REGULATIONS PERTAINING TO MATERIAL STORAGE AREAS.

DEWATERING

 THE GC SHALL IDENTIFY MASONS' AREA WITH LEGIBLE SIGNAGE ON THE SITE. TO THE EXTENT PRACTICAL ALL MASONRY TOOLS, MATERIAL, INCLUDING SAND AND SACKED CEMENT AND/OR MORTAR MATERIALS, MIX, AND EQUIPMENT SHALL BE LOCATED WITHIN THE AREA IDENTIFIED. MATERIALS VULNERABLE TO WEATHER ELEMENTS SHALL BE STORED IN CONTAINERS AT THE END OF EACH WORK DAY; SUCH MATERIALS SHALL REMAIN STORED IN CONTAINERS WHEN NOT IN USE.

ALL ON-SITE TOPSOIL MUST BE PRESERVED FOR REUSE ON THE SITE DURING REVEGETATION, UNLESS IT IS

INFEASIBLE OR UNREASONABLE TO DO SO. (NOTE: TOPSOIL STOCKPILING ON-SITE MAY BE INFEASIBLE IF SPACE

IS NOT AVAILABLE ON-SITE FOR TOPSOIL STOCKPILING OR IF LITTLE TO NO VEGETATION IS TO REMAIN UNDER

POST-CONSTRUCTION CONDITIONS. STOCKPILING OF TOPSOIL AT AN OFF-SITE LOCATION OR TRANSFER OF

ALL SOIL STOCKPILES MUST BE STABILIZED TO PREVENT EROSION AND FUGITIVE DUST. THE SURFACE OF THE

STOCKPILE MUST BE PROPERLY PROTECTED TO ELIMINATE THE RISK OF EROSION. SEE TEMPORARY SEEDING OR

STABILIZATION DETAIL. SUITABLE ALTERNATIVE MEANS OF STABILIZATION CAN BE USED, SUCH AS PROPERLY

PERIMETER SEDIMENT CONTROLS ALSO MUST BE INSTALLED AT STOCKPILE LOCATIONS TO PREVENT CONTACT WITH

. STOCKPILES MUST BE LOCATED OUTSIDE OF ANY VEGETATED BUFFER AREAS AND SHOULD BE LOCATED AS FAR

LARGE AREAS OF SOIL THAT ARE DENUDED OF VEGETATION AND HAVE NO PROTECTION FROM PARTICLES BEING

PICKED UP AND CARRIED BY WIND SHOULD BE PROTECTED WITH A TEMPORARY COVER OR KEPT UNDER CONTROL WITH WATER OR OTHER SOIL ADHERING PRODUCTS TO PREVENT SOIL PARTICLES FROM BECOMING AIRBORNE, AND

WATER TRUCKS OR OTHER DUST CONTROL AGENTS SHALL BE USED AS NEEDED DURING CONSTRUCTION TO

MINIMIZE DUST GENERATED ON THE SITE. TACKIFIERS MAY BE USED TO HOLD SOIL IN PLACE AND PREVENT

DUST. MANUFACTURER RECOMMENDATIONS FOR APPLICATION LOCATIONS AND RATES MUST BE USED FOR DUST.

CONTROL APPLICATIONS. ONLY SWPPP-SPECIFIED TACKIFIERS MAY BE USED ON THE PROJECT SITE; ANY

3. DUST CONTROL MUST BE PROVIDED BY THE GC TO A DEGREE THAT IS IN COMPLIANCE WITH APPLICABLE

4. THE USE OF MOTOR OILS AND OTHER PETROLEUM BASED OR TOXIC LIQUIDS FOR DUST SUPPRESSION OPERATIONS

5. IN ADDITION TO BMPS, GC SHALL PERFORM PER PRACTICES AND PROCEDURES WHICH MINIMIZE AND PREVENT

CHEMICAL APPLICATION NOT INCLUDED IN THE SWPPP MUST BE APPROVED, IN WRITING, BY THE CEC.

TOPSOIL TO OTHER LOCATIONS MAY ALSO BE ACCEPTABLE BUT MUST BE AUTHORIZED BY THE CEC).

AS PRACTICABLE FROM STORMWATER CONVEYANCES AND IMPOUNDMENTS AND WATER BODIES.

- 2. RUNOFF CONTROL, SUCH AS DIVERSION BERMS, SILT FENCE, SILT DIKE, OR OTHER MEANS OF CONTAINMENT SHALL BE PROVIDED TO PREVENT THE MIGRATION OF STORMWATER POLLUTANTS FROM THE MASONS' AREA. COVERED RECEPTACLES FOR DEBRIS AND TRASH DISPOSAL SHALL ALSO BE PROVIDED.
- 3. THE MASONS' AREA SHALL MEET OSHA AND OTHER REGULATORY REQUIREMENTS FOR PERSONAL PROTECTIVE EQUIPMENT (PPE), FIRE EXTINGUISHERS, ETC. GC SHALL PROVIDE SCREENING OR OTHER TECHNOLOGIES FOR MASONS' AREA TO PREVENT AIRBORNE TRANSPORT OF CEMENT DUST AND OTHER PARTICULATES DUE TO HIGH SPEED WIND OR OTHER CONDITIONS. THE LOCATION OF THE MASONS' AREA SHALL BE SHOWN ON THE



MASONS' AREA

WAL-MART STANDARD DETAIL

LAST REVISED: JUNE 2013

ANCHORED PLASTIC TARPS.

STORMWATER, INCLUDING RUN-ON.

|WAL-MART STANDARD DETAIL|

LAST REVISED: JUNE 2012

IS PROHIBITED.

WAL-MART STANDARD DETAIL

LAST REVISED: JUNE 2012

5. STOCKPILE LOCATIONS SHALL BE NOTED ON THE SITE MAPS.

FEDERAL, LOCAL AND STATE DUST CONTROL REGULATIONS.

AIRBORNE DUST OR OTHER PARTICLES FROM OCCURRING.

6. SALVAGED TOPSOIL SHALL BE SCREENED BEFORE BEING REUSED ON-SITE.

- 1. THE GC SHALL IDENTIFY FUELING AREAS WITH LEGIBLE SIGNAGE ON THE SITE. TEMPORARY ON-SITE FUEL TANKS FOR CONSTRUCTION VEHICLES SHALL MEET ALL LOCAL, STATE AND FEDERAL REGULATIONS. ALL TANKS, SINGLE AND DOUBLE WALLED, SHALL BE PROVIDED WITH SECONDARY CONTAINMENT (THAT IS CONTAINMENT EXTERNAL TO AND SEPARATE FROM PRIMARY CONTAINMENT). TANKS SHALL HAVE APPROVED SPILL CONTAINMENT WITH THE CAPACITY REQUIRED BY THE APPLICABLE REGULATIONS. SECONDARY CONTAINMENT SHALL BE CONSTRUCTED OF MATERIALS OF SUFFICIENT THICKNESS, DENSITY, AND COMPOSITION SO AS NOT TO BE STRUCTURALLY WEAKENED AS A RESULT OF CONTACT WITH THE FUEL STORED AND CAPABLE OF CONTAINING DISCHARGED FUEL FOR A PERIOD OF TIME EQUAL TO OR LONGER THAN THE MAXIMUM ANTICIPATED TIME SUFFICIENT TO ALLOW RECOVERY OF DISCHARGED FUEL. IT SHALL BE CAPABLE OF CONTAINING 110% OF THE VOLUME OF THE PRIMARY TANK IF A SINGLE TANK IS USED, OR IN THE CASE OF MULTIPLE TANKS, 150% OF THE LARGEST TANK OR 110% OF THE AGGREGATE, WHICHEVER
- 2. THE TANKS SHALL BE IN SOUND CONDITION, FREE OF RUST OR OTHER DAMAGE WHICH MIGHT COMPROMISE CONTAINMENT. FUEL STORAGE AREAS SHALL MEET ALL EPA, OSHA AND OTHER REGULATORY REQUIREMENTS FOR SIGNAGE, FIRE EXTINGUISHERS, ETC. HOSES, VALVES, FITTINGS, CAPS, FILLER NOZZLES, AND ASSOCIATED HARDWARE SHALL BE MAINTAINED IN PROPER WORKING CONDITION AT ALL TIMES. TANKS SHALL BE LOCATED TO MINIMIZE EXPOSURE TO WEATHER AND SURFACE WATER DRAINAGE FEATURES. THE LOCATION OF FUEL TANKS SHALL BE SHOWN ON THE SITE MAPS.
- 3. A SPILL PREVENTION, CONTROL AND COUNTERMEASURE (SPCC) PLAN MUST BE DEVELOPED IF ABOVEGROUND OIL STORAGE CAPACITY AT THE CONSTRUCTION SITE EXCEEDS 1,320 GALLONS OR AS SPECIFIED BY STATE.
- 4. CONTAINERS WITH A STORAGE CAPACITY OF 55-GALLONS OR LESS ARE NOT INCLUDED WHEN CALCULATING SITE STORAGE CAPACITY. THE GC SHALL WORK WITH THE CEC TO DEVELOP AND IMPLEMENT A SPCC PLAN IN ACCORDANCE WITH THE OIL POLLUTION PREVENTION REGULATION AT TITLE 40 OF THE CODE OF FEDERAL REGULATIONS, PART 112, (40 CFR 112).

FUEL AND PETROLEUM STORAGE AND USE

WAL-MART STANDARD DETAIL LAST REVISED: JUNE 2013

- 1. THE GC SHALL DESIGNATE AREAS ON THE SITE MAPS FOR EQUIPMENT CLEANING, MAINTENANCE, AND THE GC AND SUBCONTRACTORS SHALL UTILIZE SUCH DESIGNATED AREAS. CLEANING. MAINTENANCE, AND REPAIR AREAS SHALL BE PROTECTED BY A TEMPORARY PERIMETER BERM, SHALL NOT OCCUR WITHIN 150 FEET OF ANY WATERWAY, WATER BODY OR WETLAND, AND SHALL OCCUR IN AREAS LOCATED AS FAR AS PRACTICAL FROM STORM SEWER INLETS. DRIP PANS SHALL BE USED FOR VEHICLE MAINTENANCE ACTIVITIES AND RESULTANT WASTES SHALL BE DISPOSED OF IN ACCORDANCE WITH THE HAZARDOUS MATERIAL MANAGEMENT AND SPILL REPORTING PLAN NOTES INCLUDED ON THIS PLAN SHEET.
- 2. USE OF DETERGENTS FOR LARGE SCALE WASHING IS PROHIBITED (FOR EXAMPLE, WASHING VEHICLES, BUILDINGS, PAVEMENT SURFACES, ETC.). ALL WASH WATER SHALL BE DETAINED AND PROPERLY TREATED OR DISPOSED.



WAL-MART STANDARD DETAIL LAST REVISED: JUNE 2013

USING WATER FROM BASINS, TRAPS, TANKS, OR OTHER WATER CONTAINMENT AREAS FOR IRRIGATION MINIMIZES DISCHARGES FROM THE SITE, AND IT MAY SATISFY OTHER NEEDS OF THE CONSTRUCTION PROJECT, SUCH AS DUST CONTROL, VEGETATIVE ESTABLISHMENT, ETC.

- CARE SHOULD BE TAKEN THAT WATER UTILIZED FROM CONTAINMENT AREAS ON-SITE FOR CONSTRUCTION PURPOSES DOES NOT DISCHARGE OFF-SITE. IF DISCHARGE IS ANTICIPATED OR OBSERVED, DEWATERING PROCEDURES STATED IN THE DEWATERING DETAIL MUST BE FOLLOWED.
- GC SHALL IMPLEMENT IRRIGATION OR DISPERSION AS PRACTICABLE TO REDUCE WATER VOLUME IN IMPOUNDMENTS AND TO FOSTER VEGETATION GROWTH.

IRRIGATION OR DISPERSION

WAL-MART STANDARD DETAIL

LAST REVISED: JUNE 2012

- THE GC IS REQUIRED TO, AT A MINIMUM, INITIATE SOIL STABILIZATION MEASURES IMMEDIATELY WHENEVER ANY CLEARING GRADING, EXCAVATING OR OTHER EARTH DISTURBING ACTIVITIES HAVE PERMANENTLY CEASED ON ANY PORTION OF THE SITE, OR TEMPORARILY CEASED ON ANY PORTION OF THE SITE AND WILL NOT LIKELY RESUME FOR A PERIOD EXCEEDING 14 CALENDAR
- THE GC HAS 7 DAYS FROM INITIATION OF STABILIZATION TO COMPLETE SOIL PREPARATION, SEEDING, MULCHING, AND ANY OTHER REQUIRED ACTIVITIES RELATED TO THE PLANTING AND ESTABLISHMENT OF VEGETATION. THE GC ALSO HAS 7 DAYS FROM INITIATION OF STABILIZATION TO COMPLETELY INSTALL NON-VEGETATED MEASURES, IF UTILIZED.
- ALL DISTURBED AREAS MUST BE STABILIZED TEMPORARILY WITH THE USE OF FAST-GERMINATING ANNUAL GRASS/GRAIN VARIETIES APPROPRIATE FOR SITE SOIL AND CLIMATE CONDITIONS. MULCH IS REQUIRED FOR ALL SEEDING APPLICATIONS, AND ALL MULCH APPLICATIONS MUST INCLUDE A SUITABLE FORM OF MULCH ANCHORING TO MINIMIZE MOVEMENT OF MULCH BY WIND
- ALTERNATIVE STABILIZATION MEASURES TO SEEDING, SUCH AS ANCHORED MULCH APPLICATION (WITHOUT SEEDING), MAY BE UTILIZED DURING PERIODS WHEN VEGETATIVE GROWTH IS UNLIKELY (E.G. WINTER MONTHS).
- . IT IS NOT ACCEPTABLE TO ALLOW BARE SOIL TO REMAIN EXPOSED AT ANY TIME DURING THE YEAR, REGARDLESS OF WEATHER/TEMPERATURE/SITE CONDITIONS.
- ALTERNATIVE STABILIZATION MEASURES INCLUDE, BUT ARE NOT LIMITED TO: ANCHORED STRAW/HAY MULCH, WOOD CELLULOSE FIBER MULCH, SPRAY-ON SOIL GLUES/BINDERS, AND ROLLED EROSION CONTROL PRODUCTS.
- ALL ROLLED EROSION CONTROL PRODUCTS SHALL HAVE CURRENT QDOR(TM) STATUS ISSUED BY THE EROSION CONTROL TECHNOLOGY COUNCIL (ECTC) PLUS ANY STATE OR AGENCY-SPECIFIC REQUIREMENTS. EVIDENCE OF QDOR(TM) APPROVAL SHALL ACCOMPANY THE PRODUCT SHIPPED TO THE JOBSITE FOR READY IDENTIFICATION BY THE CONTRACTOR OR AGENCY
- ROLLED EROSION CONTROL PRODUCTS (NETS, BLANKETS, TURF REINFORCED MATES) AND VEGETATED AREAS NOT MEETING REQUIRED VEGETATIVE DENSITIES FOR FINAL STABILIZATION MUST BE INSPECTED DAILY. RILING, RUTTING AND OTHER SIGNS OF EROSION INDICATE THE SPECIFIED EROSION CONTROL DEVICE IS NOT FUNCTIONING OR INSTALLED PROPERLY AND/OR ADDITIONAL

TEMPORARY SEEDING OR STABILIZATION

WAL-MART STANDARD DETAIL

LAST REVISED: JUNE 2012

- PERMANENT STABILIZATION SHALL BE ACCOMPLISHED IN ALL DISTURBED AREAS BY COVERING THE SOIL WITH PAVEMENT, BUILDING STRUCTURES, VEGETATION, OR OTHER FORMS OF SOIL STABILIZATION.
- THE GC IS REQUIRED TO INITIATE PERMANENT SOIL STABILIZATION MEASURES IMMEDIATELY UPON REACHING FINAL GRADE. FOR THOSE AREAS NOT AT FINAL GRADE THAT WILL NOT BE DISTURBED FOR GREATER THAN 14 DAYS , THE CONTRACTOR SHOULD INITIATE TEMPORARY STABILIZATION PER THE TEMPORARY SEEDING OR STABILIZATION DETAIL THE GC HAS 7 DAYS FROM INITIATION OF STABILIZATION TO COMPLETE SOIL PREPARATION, SEEDING, MULCHING, AND ANY OTHER
- REQUIRED ACTIVITIES RELATED TO THE PLANTING AND ESTABLISHMENT OF VEGETATION. THE GC ALSO HAS 7 DAYS FROM INITIATION OF STABILIZATION TO COMPLETELY INSTALL NON-VEGETATED MEASURES, IF UTILIZED.
- 4. SOILS MUST BE PREPARED BEFORE INSTALLATION OF SOD OR SEED. SEE 02900 SPECIFICATION FOR INSTRUCTION ON PROPER
- AT THE COMPLETION OF GROUND-DISTURBING ACTIVITIES, THE ENTIRE SITE MUST HAVE PERMANENT VEGETATIVE COVER MEETING VEGETATIVE DENSITY REQUIREMENTS IN THE GENERAL PERMIT, OR MULCH PER LANDSCAPE PLAN, IN ALL AREAS NOT COVERED BY HARDSCAPE (STONE, PAVEMENT, BUILDINGS, ETC.).
- SEEDED AREAS SHALL BE PROTECTED WITH STRAW MULCH, HYDRAULIC MULCH OR A ROLLED EROSION CONTROL PRODUCT. STRAW MULCH MUST BE TACKIFIED OR CRIMPED BY DISC OR OTHER MACHINERY, AND ROLLED EROSION CONTROL PRODUCTS MUST BE INSTALLED PER MANUFACTURER RECOMMENDATIONS. ONLY ROLLED EROSION CONTROL PRODUCTS ARE PERMITTED TO BE USED IN
- ALL AREAS TO BE SEEDED MUST MEET TOPSOIL DEPTH, PH AND ORGANIC CONTENT REQUIREMENTS AS SPECIFIED IN THE 02900 SPECIFICATION - PLANTING OR XERISCAPE SPECIFICATION.
- 8. FINAL SITE STABILIZATION IS ACHIEVED WHEN PERENNIAL VEGETATIVE COVER PROVIDES PERMANENT STABILIZATION WITH A EXCLUSIVE OF AREAS THAT ARE COVERED WITH ROCK (CRUSHED GRANITE, GRAVEL, ETC.) OR LANDSCAPE MULCH, PAVED OR HAVE

PERMANENT SEEDING, SOD OR MULCHING

WAL-MART STANDARD DETAIL LAST REVISED: JUNE 2012

- CONSIDERATION MUST BE GIVEN TO ANTICIPATED CLIMATE AND SEASONAL CONDITIONS WHEN PLANTING SEED. SEED SHALL BE FREE OF WEEDY SPECIES AND APPROPRIATE FOR SITE SOILS AND REGIONAL CLIMATE. SEED AND MULCH PER THE CONSTRUCTION DRAWINGS AND THE 02900 PLANTING SPECIFICATION IMMEDIATELY AFTER TOPSOIL IS APPLIED AND FINAL
- THE SITE HAS ACHIEVED FINAL STABILIZATION ONCE ALL AREAS ARE COVERED WITH BUILDING FOUNDATION OR PAVEMENT, OTHER LANDSCAPING COVER (STONE, MULCH, ETC.), OR HAVE A STAND OF GRASS WITH A MINIMUM OF 70 PERCENT DENSITY
- OVER THE ENTIRE VEGETATED AREA, OR GREATER IN ACCORDANCE WITH THE GENERAL PERMIT REQUIREMENTS. VEGETATED AREAS MUST BE WATERED, FERTILIZED, AND RESEEDED AS NEEDED TO ACHIEVE THIS REQUIREMENT.
- THE VEGETATIVE DENSITY MUST BE MAINTAINED THROUGH PROJECT COMPLETION TO BE CONSIDERED STABILIZED. PROTECTED BY EROSION CONTROL BLANKETS ARE NOT PERMANENTLY STABILIZED UNTIL THE APPLICABLE GENERAL PERMIT REQUIREMENT FOR FINAL VEGETATIVE DENSITY IS ACHIEVED.
- RIP-RAP, MULCH, GRAVEL, DECOMPOSED GRANITE OR OTHER EQUIVALENT PERMANENT STABILIZATION MEASURES MAY BE EMPLOYED IN LIEU OF VEGETATION BASED ON SITE-SPECIFIC CONDITIONS, DESIGN AND GOVERNING AUTHORITY APPROVAL. ALL SEEDED AREAS SHALL BE INSPECTED REGULARLY TO CONFIRM THAT A HEALTHY STAND OF GRASS IS MAINTAINED.

SEEDING/VEGETATION REQUIREMENTS

WAL-MART STANDARD DETAIL LAST REVISED: JUNE 2012

DEVELOPER/OWNER: WAL-MART REAL ESTATE BUSINESS TRUST MAIL STOP 5570 2001 SE 10TH STREET **BENTONVILLE, AR 72716-5570** 479-204-1195 SITE OPERATOR/GENERAL CONTRACTOR:

SUPERINTENDENT:

GC MUST SIGN ALL PLAN SHEETS AND ANY NEW PLAN SHEETS ISSUED BY THE CEC.

DRAWN BY: _MH 11-20-14 SCALE:

COUNT VANDERBURGH SED

9

EB


INDIANA

ONTROL


O

SEDIMENTATION AND EROSIO

<u>N.T.S.</u> SHEET



MANUFACTURER STANDARD DETAIL



ALL SITE ACCESS MUST BE CONFINED TO THE CONSTRUCTION EXIT(S). BARRICADE TO PREVENT USE

OF ANY LOCATIONS OTHER THAN THE CONSTRUCTION EXIT(S) WHERE VEHICLES OR EQUIPMENT MAY

CONTRACTOR TO LOCATE TEMPORARY CONSTRUCTION FENCING, JERSEY BARRIERS, OR BOTH ALONG

PROVIDE SEDIMENT TRAP ON DOWN GRADIENT SIDE (OR BOTH SIDES) AS REQUIRED. SEDIMENT TRAP SHALL BE LOCATED OUTSIDE OF THE RIGHT-OF-WAY AND AT A MINIMUM SETBACK DISTANCE AS

IF THE ACTION OF VEHICLES TRAVELING OVER THE GRAVEL CONSTRUCTION EXIT(S) IS NOT SUFFICIENT

LOCATIONS WHERE VEHICLES ENTER AND EXIT THE SITE MUST BE INSPECTED FOR EVIDENCE OF

ANY SEDIMENT DEPOSITED ON THE ROADWAY SHALL BE SWEPT AS NECESSARY (AND WITHIN THE SAME DAY AS DISCOVERY) AND DISPOSED OF IN AN APPROPRIATE MANNER. SEDIMENT SHALL NOT

EXIT(S) SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOW OF MUD

BEYOND THE EXIT(S). THIS MAY REQUIRE PERIODIC TOP DRESSING OF THE CONSTRUCTION EXIT(S) AS

CONTRACTOR SHALL BE PERMITTED TO TURN THE STONE WHEN THE SURFACE BECOMES SMOOTH AND

EFFECTIVE. AT SUCH A TIME THE CONTRACTOR SHALL REMOVE THE INEFFECTIVE STONE AND REPLACE

CONSTRUCTION EXIT

SURFACE VOIDS ARE FILLED TO MAINTAIN EFFECTIVENESS OF CONSTRUCTION EXIT UNTIL SUCH TIME

THAT VOIDS BELOW THE SUBFACE BECOME FILLED AND THE CONSTRUCTION EXIT IS NO LONG

IF EXIT BMP IS STILL INEFFECTIVE, GC MUST CONTACT THE ENGINEER AND SUBMIT AN RFI AS

SEDIMENT TRACKING BEYOND THE PERMITTED PROJECT AREA. ALL MATERIALS SPILLED, DROPPED, WASHED OR TRACKED FROM VEHICLES ONTO ROADWAYS OR INTO STORM DRAINS MUST BE REMOVED.

TO PREVENT TRACKING OF DIRT, DUST OR MUD, THEN TIRES MUST BE WASHED BEFORE THE VEHICLES ENTER A PUBLIC ROAD. ALL WASH WATER MUST BE ROUTED TO A SEDIMENT TRAP OR OTHER

THE SIDES OF THE CONSTRUCTION EXIT TO PREVENT CONSTRUCTION TRAFFIC FROM SHORT

TREATMENT AREA AND SHALL NOT BE DIRECTLY DISCHARGED OFF—SITE.

ACCESS THE SITE.


CONDITIONS DEMAND


LAST REVISED: JUNE 2013


CIRCUITING/BYPASSING THE EXIT.


REQUIRED PER LOCAL JURISDICTION.

BE WASHED INTO STORM SEWER SYSTEMS.










OVERFLOW

TRUCK DOCK DRAIN

TRUE DAM



GENERAL NOTES

1. EROSION EELS™ USED IN PERIMETER CONTROL APPLICATIONS SHALL HAVE A SPECIFICATION MIXTURE 1.0 OR 2.0.

A. MIXTURE SPECIFICATION 1.0. A FILTER MATERIAL COMPRISED OF 100% RUBBER SHREDS. THE RUBBER SHALL BE DERIVED FROM RECYCLED TIRES AND SHALL BE SHREDDED TO PRODUCE A MAXIMUM PARTICLE SIZE OF +/- 3/4 INCH. B. MIXTURE SPECIFICATION 2.0. A FILTER MIXTURE COMPRISED OF 100% SHREDDED RUBBER DERIVED FROM RECYCLED TIRES. MAXIMUM PARTICLE SIZE

2. LENGTHS OF EROSION EELS™ SHALL BE EITHER A NOMINAL +/-10 FT. OR +/- 4.5 FT. NOMINAL DIAMETER SHALL BE +/-9.5 INCHES FOR PERIMETER CONTROLS AND $\pm /-20$ INCHES FOR CHECK DAM APPLICATIONS.

3. EROSION EELS™ CAN BE PLACED AT THE TOP, ON THE FACE, OR AT THE TOE OF SLOPES TO INTERCEPT RUNOFF, REDUCE FLOW VELOCITY, RELEASE THE RUNOFF AS SHEET FLOW AND PROVIDE REMOVAL OF™ SEDIMENT FROM THE RUNOFF.

4. EROSION EELS™ SHALL BE INSTALLED ALONG THE GROUND CONTOUR, AT THE TOE OF SLOPES, AT AN ANGLE TO THE CONTOUR TO DIRECT FLOW, AS A DIVERSION BERM, AROUND INLET STRUCTURES, IN A DITCH AS A CHECK DAM TO HELP REDUCE SUSPENDED SOLIDS LOADING AND RETAIN SEDIMENT OR AS A CENERAL FULTER FOR ANY DISTURBED COURSE. RETAIN SEDIMENT, OR AS A GENERAL FILTER FOR ANY DISTURBED SOIL AREA.

5. NO TRENCHING IS REQUIRED FOR INSTALLATION OF EROSION EELS

6. PREPARE BED FOR EEL INSTALLATION BY REMOVING ANY LARGE DEBRIS INCLUDING ROCKS, SOIL CLODS, AND WOODY VEGETATION. EROSION EELS CAN ALSO BE PLACED OVER PAVED SURFACES INCLUDING CONCRETE AND ASPHALT WITH NO SURFACE PREPARATION REQUIRED. 7. RAKE BED AREA WITH A HAND RAKE OR BY DRAG HARROW.

8. DO NOT PLACE EEL DIRECTLY OVER RILL AND GULLIES UNTIL AREA HAS BEEN HAND-EXCAVATED AND RAKED TO PROVIDE A LEVEL BEDDING SURFACE. ALL SURFACES SHALL BE UNIFORMLY COMPACTED FOR MAXIMUM SEATING OF EELS IN PLACE.

9. FOR LOCATIONS WHERE EELS WILL BE PLACED IN CONCENTRATED FLOWS (SUCH AS CHECK DAMS, INLET PROTECTION) AND FOR PERIMETER CONTROLS AT PRIMARY DISCHARGE LOCATIONS, BED THE EELS IN A JUTE MESH CRADLE PER THE DETAILED DRAWINGS.

10. FOR DITCH APPLICATIONS, THE MAXIMUM DRAINAGE AREA SHALL BE 10 ACRES.

11. IF MORE THAN ONE EROSION EEL™ IS PLACED IN A ROW, PREPARE JOINTS PER DETAIL E1-B1.

12. EROSION EELS™ SHALL REMAIN IN PLACE UNTIL FULLY ESTABLISHED VEGETATION HAS COMPLETELY DEVELOPED OR UNTIL THE STORAGE CAPACITY/FUNCTIONAL LIFE OF THE EEL HAS BEEN EXHAUSTED (REQUIRING REPLACEMENT WITH NEW EELS).

13. ANCHORING POSTS FOR CHECK DAM APPLICATIONS SHALL HAVE A MINIMUM WEIGHT OF 1.25 LBS/FT STEEL T-POSTS (5 TO 7 FT. LENGTHS) ROLLED FROM HIGH CARBON STEEL. POSTS SHOULD BE HOT-DIP GALVANIZED OR COATED WITH A WEATHER-RESISTANT PAINT FOR STEEL APPLICATION. POSTS SHOULD BE EQUIPPED WITH A METAL ANCHOR PLATE. INSTALL PER DETAILS ON THIS SHEET.

14. PLACE T-POSTS THROUGH HANDLE OF BAGS. DO NOT DRIVE POSTS THROUGH EROSION EELS . T-POSTS ARE TO BE EMBEDDED A MINIMUM OF 3 FT. INTO GROUND ON STEEP SLOPES GREATER THAN 25%.

DEVELOPER/OWNER: WAL-MART REAL ESTATE BUSINESS TRUST MAIL STOP 5570 2001 SE 10TH STREET BENTONVILLE, AR 72716-5570 479-204-1195 SITE OPERATOR/GENERAL CONTRACTOR: SUPERINTENDENT

> GC MUST SIGN ALL PLAN SHEETS AND ANY NEW PLAN SHEETS ISSUED BY THE CEC.

PROJ. MGR.: TTR PROJ. ASSOC.: BAM 11-20-14 N.T.S. SHEET

ONTRO

NO.


AND


INDIAN


OUNT


ERBURG


AND























PROJ. MGR.: __TTR__ PROJ. ASSOC.: BAM DRAWN BY: DATE: WALEVI4

IMPORTANT: GC MUST SIGN ALL PLAN SHEETS AND ANY NEW PLAN SHEETS ISSUED BY THE CEC.

<u>N.T.S.</u> SCALE: OF

11-20-14

120866

S

S

AND

EROSION

SOIL EROSION/SEDIMENTATION CONTROL OPERATION TIME SCHEDULE NOTE: GENERAL CONTRACTOR TO COMPLETE TABLE WITH THEIR ESTIMATED PROJECT SCHEDULE AUGSEP OCT NOV DEC JAN FEB MARAPR MAY JUN JUL AUGSEP OCT NOV DEC JAN FEB MARAPR MAY JUN JUL AUG CONSTRUCTION SEQUENCE TEMPORARY CONSTRUCTION EXITS TEMPORARY CONTROL MEASURES SEDIMENT CONTROL BASIN(S)/TRAP(S) STRIP & STOCKPILE TOPSOIL ROUGH GRADING STORM FACILITIES SITE CONSTRUCTION FINISH GRADING PERMANENT CONTROL STRUCTURES FOUNDATION / BUILDING CONSTRUCTION LANDSCAPING/SEED/FINAL STABILIZATION) CONTRACTOR MUST COMPLETE TABLE WITH ESTIMATED DATES OR PROJECT ACTIVITIES PRIOR TO BMP CERTIFICATION. 2) TIME SCHEDULE MUST COINCIDE WITH THE SWPPP IMPLEMENTATION SEQUENCE. | WAL-MART STANDARD DETAIL | LAST REVISED: APRIL 30, 2011

	ACREAGE SUMMARY (IN ACRES)	
1	WAL-MART PROPERTY AREA	30.81
2	PERMITTED AREA WITHIN WAL-MART PROPERTY	28.50
3	PERMITTED AREA OUTSIDE OF WAL-MART PROPERTY	6.00
4	TOTAL PERMITTED PROJECT AREA (MUST MATCH NOI)	34.50
5	IMPERVIOUS AREA BEFORE PROJECT (On-site & Off-site)	4.00
6	IMPERVIOUS AREA AT COMPLETION (On-site & Off-site)	25.00
7	PERVIOUS AREA AT COMPLETION (On-site & Off-site)	9.50

OFF-SITE RUN-ON SUMMARY					
OFF-SITE DRAINAGE AREA	FLOW (CFS)	AREA (ACRES)	AVERAGE SLOPE	MAXIMUM SLOPE	COVER TYPE
AREA 1	14.13	15.03	1.25%	33.33%	AGRICULTURAL

WAL-MART STANDARD DETAIL LAST REVISED: JUNE 2012

| WAL-MART STANDARD DETAIL | LAST REVISED: JUNE 2013

RUNOFF COEFFICIENT SUMMA	ARY
RE-CONSTRUCTION RUNOFF COEFFICIENT [OR SCS TR-55 CURVE NUMBER]:	CN = 87
OST-CONSTRUCTION RUNOFF COEFFICIENT [OR SCS TR-55 CURVE NUMBER]:	CN =91

SITE LOCATION SUMMARY			
ADDRESS:	NWC OF RT 57 AND NEW HARMONY/ BOONVILLE RD, EVANSVILLE, IN 47725		
CENTER OF SITE:			
LATITUDE:	38°05'14" N OR 38.087346°N		
LONGITUDE:	87°29'45" W OR 87.495865°W		
ADJACENT SURROUNDING PROPERTIES:	ADJACENT LAND NORTH OF THE SITE CONTAINS CROP FIELDS. ADJACENT LAND EAST OF THE SITE CONTAINS CROP FIELDS. ADJACENT LAND WEST OF THE SITE CONTAINS CROP FIELDS AND RESIDENTIAL USE. ADJACENT LAND SOUTH OF THE SITE IS RESIDENTIAL. ADJACENT LAND SOUTHEAST OF THE SITE IS GENERAL INDUSTRIAL USE.		

WAL-MART STANDARD DETAIL

LAST REVISED: JUNE 2013

ADDRESS:	NWC OF RT 57 AND NEW HARMONY/ BOONVILLE RD, EVANSVILLE, IN 47725		
CENTER OF SITE:			
LATITUDE:	38°05'14" N OR 38.087346°N		
LONGITUDE:	87°29'45" W OR 87.495865°W		
ADJACENT SURROUNDING PROPERTIES:	ADJACENT LAND NORTH OF THE SITE CONTAINS CROP FIELDS. ADJACENT LAND EAST OF THE SITE CONTAINS CROP FIELDS. ADJACENT LAND WEST OF THE SITE CONTAINS CROP FIELDS AND RESIDENTIAL USE. ADJACENT LAND SOUTH OF THE SITE IS RESIDENTIAL. ADJACENT LAND SOUTHEAST OF THE SITE IS GENERAL INDUSTRIAL USE.		

SITE TOPOGRAPHY SUMMARY		
LOWEST ELEVATION OF PROJECT SITE:	EXISTING: 387.2 PROPOSED: 380.5	
HIGHEST ELEVATION OF PROJECT SITE:	EXISTING: 395.3 PROPOSED: 396.0	
PERCENT SLOPE VARIATION:	THE EXISTING SLOPES VARY FROM 0.01% TO 6.00% WITHIN PAVED AREAS AND 0.20% TO 10.00% WITHIN LANDSCAPED AREAS. PROPOSED SLOPES WILL VARY FROM 0.50% TO 3.00 WITHIN PAVED AREAS AND 1.00% TO 25.00% WITHIN LANDSCAPED AREAS.	
TOPOGRAPHY CHANGES:	THE EXISTING SITE SLOPES FROM THE SOUTHWEST TO THE NORTHEAST TOWARDS SCHLENSKER DITCH WHICH FLOWS FROM WEST TO EAST. THE PROPOSED WAL-MART SUPERCENTER WILL HAVE A FINISHED FLOOR OF 396.00. THE PROPOSED GRADING WILL MAINTAIN THE EXISTING DRAINAGE PATTERN ON-SITE. A STORMWATER DETENTION BASIN WILL BE CONSTRUCTED AT THE NORTHERN PORTION OF THE SITE.	
VEGETATION:	THE EXISTING VEGETATION COVERING THE SITE CONSISTS MAINLY OF AGRICULTURAL LAND. THE DEVELOPED LOT WILL CONSIST OF GRASSES, SHRUBS, TREES AND PLANTS IN THE LANDSCAPED ISLANDS AND PERIMETER LANDSCAPED REGIONS.	
AVERAGE SLOPE:	THE AVERAGE SLOPE THROUGH THE SITE IS 2.50%	

2014 WAS OBSERVED TO RANGE BETWEEN 6 AND 8 FEET. NOTE: THE ABOVE SOILS INFORMATION IS FOR INFORMATION ONLY AND SHOULD NOT BE USED FOR BIDDING PURPOSES, WAL-MART STANDARD DETAIL LAST REVISED: JUNE 2012

INC. DATED JUNE 16, 2014.

SITE SOILS SUMMARY

SOIL TYPE AND TEXTURE:

AVERAGE DEPTH OF TOPSOIL:

AVERAGE DEPTH TO GROUNDWATER:

A GEOTECHNICAL INVESTIGATION WAS PERFORMED BY TERRACON

CONSULTANT, INC. AND IS SUMMARIZED IN THE REPORT DATED JUNE 16, 2014. THE INVESTIGATION REVEALED LOWER STRENGTH LEAN CLAY SOILS AND SILTY CLAY SOILS WITH RELATIVELY HIGH MOISTURE CONTENTS BELOW TOPSOIL TO DEPTHS OF 3 TO 10 FEET. IN SOME INSTANCES, SANDY LEAN CLAY (CL) AND CLAYEY SAND (SC) WERE FOUND BELOW THE LEAN CLAY (CL), BUT GENERALLY BORINGS TERMINATED WITH LEAN CLAY (CL). BORING TERMINATION DEPTHS RANGED FROM 10 FEET TO 30 FEET.

AVERAGE TOP SOIL DEPTH IS 4" RANGING FROM 2 TO 4 INCHES IN DEPTH ACCORDING TO THE GEOTECHNICAL REPORT BY TERRACON CONSULTING,

GEOTECHNICAL REPORT BY TERRACON CONSULTING, INC. DATED JUNE 16,

THE AVERAGE GROUNDWATER DEPTH, ACCORDING TO THE

SITE RAINFALL SUMMARY JAN FEB MAR APR MAY JUN JUL AUG SEP OCT NOV DEC 3.23 | 3.45 | 4.50 | 4.58 | 5.05 | 3.98 | 3.93 | 3.23 | 3.26 | 3.41 | 4.33 | RAINFALL IN INCHES

THE TOTAL AVERAGE ANNUAL RAINFALL FOR THE PROJECT AREA IS: 46.93 INCHES THE DESIGN RAIN EVENT FOR THE PROJECT IS: PRE VS. POST DEVELOPMENT EVALUATIONS WERE PERFORMED BASED UPON A 3RD QUARTILE HUFF DISTRIBUTION, 24-HOUR STORM FOR 10-(4.70"), 25-(5.39") AND 100-(6.55") YEAR STORM EVENTS. THE PROPOSED SOTRM SEWER SYSTEM HAS BEEN DESIGNED FOR THE 10-YEAR STORM BASED UPON MANNING'S EQUATION FOR PIPES FLOWING FULL.

WAL-MART STANDARD DETAIL LAST REVISED: JUNE 2012

| WAL-MART STANDARD DETAIL

LAST REVISED: JUNE 2012

BUFFER NAME	BUFFER AREA (ACRES) - INCLUDE ORIENTATION DESCRIPTION AND RELATIONSHIP TO WATERS OF THE US
TREE PRESERVATIONS	APPROXIMATELY 30' TO 170' OF THE NORTHERN PORTION OF THE SITI IS VEGETATED WOODED AREA IMMEDIATELY ADJACENT TO SCHLENSKER DITCH. NO DISTURBANCE IS PROPOSED WITHIN THIS AREA, AND THE VEGETATED AREA BUFFER WILL REMAIN.

1. PRESERVE VEGETATED AREAS THROUGHOUT THE CONSTRUCTION PROJECT. ESTABLISH VEGETATION IN DISTURBED AREAS PER STABILIZATION DETAILS.

WAL-MART STANDARD DETAIL

LAST REVISED: JUNE 2012


DELINEATE AND PROTECT VEGETATED STRIPS OR BUFFERS PRIOR TO EARTH DISTURBING ACTIVITIES. 3. INSPECT VEGETATED STRIPS OR BUFFERS AS REQUIRED. WAL-MART STANDARD DETAIL LAST REVISED: JUNE 2013

> DEVELOPER/OWNER: WAL-MART REAL ESTATE BUSINESS TRUST MAIL STOP 5570 2001 SE 10TH STREET BENTONVILLE, AR 72716-5570 479-204-1195 SITE OPERATOR/GENERAL CONTRACTOR: SUPERINTENDENT:

> > IMPORTANT:
> > GC MUST SIGN ALL PLAN SHEETS AND ANY NEW
> > PLAN SHEETS ISSUED BY THE CEC.


SED

PROJ. ASSOC.: BAM 11-20-14 N.T.S. SHEET



PROJ. ASSOC.: BAM <u>11-20-14</u> <u>1"=60'</u>

DEMOLITION VANDERBURGH COUNTY, INDIANA AND CONDITIONS



33

SUPERCENTER

SED

COUNTY, INDIANA

VANDERBURGH

DIMENSIONAL


SITE


7.5" CONCRETE PAVEMENT W/ 6 X 6 W1.4 WWF


4" COMPACTED AGGREGATE BASE COURSE, NO. 53


- CONTRACTOR SHALL REFER TO THE ARCHITECTURAL PLANS FOR EXACT LOCATIONS AND DIMENSIONS OF VESTIBULES, SLOPE PAVING, SIDEWALKS, EXIT PORCHES, TRUCK DOCKS, PRECISE BUILDING DIMENSIONS AND EXACT BUILDING UTILITY ENTRANCE LOCATIONS.
- 4. ALL CURBED RADII ARE TO BE 3' UNLESS OTHERWISE NOTED. STRIPED RADII ARE TO
- 5. ALL DIMENSIONS AND RADII ARE TO THE FACE OF CURB OR BUILDING FOUNDATION
- CONTRACTOR SHALL BE RESPONSIBLE FOR ALL RELOCATIONS, (UNLESS OTHERWISE NOTED ON PLANS) INCLUDING BUT NOT LIMITED TO, ALL UTILITIES, STORM DRAINAGE, SIGNS, TRAFFIC SIGNALS AND POLES, ETC. AS REQUIRED. ALL WORK SHALL BE IN ACCORDANCE WITH GOVERNING AUTHORITIES REQUIREMENTS AND PROJECT SITE WORK
- 8. SITE BOUNDARY, TOPOGRAPHY, UTILITY AND ROAD INFORMATION TAKEN FROM A SURVEY
- 10. NO WETLANDS WERE PRESENT ON THIS SITE AS INDICATED BY THE LETTER FROM THE
- TO BE KEPT FREE OF JOB TRAILERS AND STORAGE AFTER THE CONTRACT MILESTONE DATE FOR THE OUTLOT. WM GENERAL CONTRACTOR TO PROVIDE CLEAR ACCESS FOR OUTLOT CONTRACTOR TO THE SPECIFIC PARCEL AT ALL TIMES AFTER MILESTONE DATE.PURCHASER OF OUTLOT TO PROVIDE PERMIT DOCUMENTS AND SWPPP REQUIRED
- 15. ALL PROPOSED CURB AND GUTTER SHALL BE MODIFIED B6.12 UNLESS OTHERWISE
- SUBSEQUENT ARCHITECTURAL CHANGES MAY EXIST. THEREFORE CONTRACTOR SHALL REFER TO ARCHITECTURAL PLANS FOR PRECISE BUILDING DIMENSIONS AND NOTIFY THE
- 18. ALL HANDICAP RAMPS SHALL BE CONSTRUCTED WITH A MAXIMUM CROSS SLOPE OF
- 20. DEPRESS CURB AND GUTTER AT ALL SIDEWALK AND PATH LOCATIONS FOR HANDICAP
- 22. ALL ROADWAY AND PARKING LOT IMPROVEMENTS SHALL BE COMPLETED IN ACCORDANCE WITH THE APPLICABLE SECTIONS OF THE STANDARD SPECIFICATIONS FOR ROAD AND


PROJ. MGR.: TTR PROJ. ASSOC.: BAM DRAWN BY: MH 11-20-14 1"=60' SHEET















| Color | Colo


WAL-MART SUPERCENTER NO. 3.
DERBURGH COUNTY, INDIANA


SED


PROJ. MGR.: TTR
PROJ. ASSOC: BAM


SHEET 19 OF 37 WALEVI4 120866





























NOTE:

Landscape Notes:

- 1. All landscape areas to receive a minimum of 4" of topsoil. See 2900 Specification.
- All plant material shall be healthy, vigorous, and free of pests and disease.
- 3. All plant material shall be container grown or balled and burlapped as indicated in the plant
- All trees shall have a straight trunk and full head and meet all requirements specified.
- 5. All materials are subject to the approval of the Landscape Architect before, during, and after installation.
- 6. All trees must be guyed or staked as shown in the details.
- 7. All planting areas shall be completely mulched as specified.
- 8. Prior to construction, the contractor shall be responsible for locating all underground utilities and shall avoid damage to all utilities during the course of the work. Locations of existing buried utility lines shown on the plans are based upon best available information and are to be considered approximate. It shall be the responsibility of the contractor 1) to verify the locations of utility lines on and adjacent to the work area 2) to protect all utility lines during the construction period 3) to repair any and all damage to utilities, structures, site appurtenances, etc. which occurs as a result of the construction.
- 9. The contractor shall be responsible for verifying all quantities shown on these plans before pricing the work.
- 10. Contractor shall be responsible for delivery schedule and protection between delivery and planting per specifications to maintain healthy plant conditions.
- 11. The contractor shall be responsible for fully maintaining (including but not limited to: watering, spraying, mulching, fertilizing, etc.) all of the plant materials and lawn for the period of time shown in the 02900 spec.
- completion) shall be promptly removed from the site and replaced with material of the same species, quantity, and size and meeting all plant list specifications. 13. The contractor shall completely guarantee all plant material for a period defined in the

12. Any plant material which is diseased, distressed, dead, or rejected (prior to substantial

- 02900 spec. The contractor shall promptly make all replacements during the normal planting season.
- 14. After being dug at the nursery source, all trees in leaf shall shall be acclimated for two (2) weeks under a mist system prior to installation.
- 15. Standards set forth in "American Standard for Nursery Stock" represent guideline specifications only and shall constitute minimum quality requirements for plant material.
- 16. Where shown on the plans and details, planting beds are to be completely covered with a hardwood mulch from a local source harvested in a sustainable manner to a minimum depth of four inches.
- 17. Refer to Walmart specifications for information needed for implementation of planting
- 18. Weed mat is required in landscaped islands as specified.
- 19. All plant material quantities shown are approximate, contractor shall be responsible for complete coverage of all planting beds at spacing shown.
- 20. This plan is to be implemented cooperatively with SWPPP plan, as needed, to maximize the effectiveness of the SWPPP plan for this site.
- 21. The contractor is encouraged to complete temporary or permanent seeding or sodding in stages for soil stabilization as areas are completed after grading.
- 22. This plan does not present any temporary stabilization required as part of SWPPP plan.

Utility Notes:

- 1. The landscape contractor is required to contact Julie, the Municipal or County Public Works Department, and any other public or private agency necessary for utility location prior to any construction.
- 2. This drawing is a part of a complete set of bid documents, specifications, additional drawings, and exhibits. Under no circumstances should these plans be used for construction purposes without examining actual locations of utilities on site, and reviewing all related documents.
- 3. The location of all underground utilities are located on the engineering drawings for this project. The most current revision is used in making this document. Underground utilities exist throughout this site and must be located prior to any construction activity. Where underground utilities exist, field adjustment may be necessary and must be approved by a representative of the owner, neither the owner nor the Landscape Architect assumes any responsibility whatsoever, in respect to the contractors accuracy in locating the indicated plant material, and under no circumstances should these plans be used without referencing the above mentioned documents.




NEW


NO. INDI/ COUNTY, II LANDSCAPE


SUPERCENTER ERBURGH (WAL-MART PROPOSED


PROJ. MGR.: TTR PROJ. ASSOC.: BAM DRAWN BY: AS 11-20-14 DATE: SCALE: <u>N.T.S.</u>


SHEET |WALEVI4 120866|























































SEAL

PROJ. MGR.: TTR PROJ. ASSOC.: BAM 11-20-14 DATE: N.T.S. SCALE:

337

Ö N

SUPERCENTER

WAL-MART

PROPOSED

INDIANA

COUNTY,


VANDERBURGH


AILS


DET


ONSTRUCTION


SHEET WALEV14 120866



















PROPOSED WAL-MART S

LOW BROT WART

LULY

LOW BROT WALL

LULY

LOW BROT WALL

LULY

LOW BROT WALL

LULY

LOW BROT WALL

LULY

Š.

SUPERCENTER

COUNTY, INDIANA

PROJ. ASSOC.: BAM
DRAWN BY: AS
DATE: 11-20-14
SCALE: N.T.S.
SHEET

34 OF 37