


ASHWOOD PHASE IA

DAILY ENTERED FOR TAXATION SUBJECT
 TO FINAL ACCEPTANCE FOR TRANSFER
 RECEIVED FOR RECORD
 at 10:20 A.M.
 JUL 7 2000
 JUL 7 2000
 Plat Book Q-82
 Page 82
 BETTY J. HERMANN RECORDER
 VANDERBURGH COUNTY
 2000R00019263



LEGAL DESCRIPTION
 Part of the Northeast Quarter of Section 11, Township 6 South, Range 10 West lying in Center Township, Vanderburgh County, Indiana described as follows:

Beginning at a point located by commencing at the Northeast corner of said Quarter Section thence North 89 degrees 50 minutes 16 seconds West along the North line thereof a distance of 1269.17 feet, thence South 0 degrees 07 minutes 27 seconds West a distance of 1394.34 feet, to the place of beginning of this description, thence South 0 degrees 07 minutes 27 seconds West a distance of 219.49 feet, thence South 34 degrees 49 minutes 12 seconds West a distance of 263.52 feet to the beginning of a curve to the left having a radius of 125 feet, thence Northwesterly along said curve a distance of 140.12 feet (chord = 132.90 feet at a bearing of North 31 degrees 59 minutes 20 seconds West) to the end of said curve, thence North 64 degrees 06 minutes 08 seconds West a distance of 31.36 feet to the Southeast corner of lot 15 Ashwood Phase I as recorded in Plat Book Q Page 17 in the Office of the Recorder of Vanderburgh County, Indiana, thence North 25 degrees 53 minutes 52 seconds East along the Easterly line of said lot 15 a distance of 250.00 feet, thence North 0 degrees 10 minutes 00 seconds East along said Easterly line a distance of 144.47 feet to the Northeast corner of said lot 15, thence South 89 degrees 36 minutes 08 seconds East a distance of 140.07 feet to the place of beginning and containing 1.609 acres more or less.

DRAINAGE IMPROVEMENTS
 The Individual Lot Owners shall be responsible, including financially, for maintaining that part of the storm water drainage system and its easements which exists on his or her property in proper working order including:



1. Mowing grass, controlling weeds, and maintaining the designed cover of the waterways, storage basins, and easements in accordance with applicable ordinances.
2. Keeping all parts of the storm water drainage system operating at all times as designed and as constructed; and free of all trash, debris, and obstructions to the flow of water.
3. Keeping the channels, embankments, shorelines, and bottoms of waterways and basins free of all erosion and sedimentation.
4. Maintaining that part of the storm water drainage system which lies on his or her property in accordance with the conditions described on the approved street and/or drainage plans on file in the County Surveyor's Office; and in compliance with the County Drainage Ordinance.
5. Preventing all persons or parties from causing any unauthorized alterations, obstructions, or detrimental actions from occurring to any part of the storm water drainage system and easements which lies on his or her property.
6. The Repair Fund established for this Project will pay the costs of repairing structural failures in the storm sewer pipes, pipe collars, drop boxes, aprons, inlets, manholes, junction boxes, and the piped or paved outlet structures of the storm water control basins all of which are parts of the approved and constructed storm water drainage system shown on the as-built plans for this Subdivision; and which are in drainage easements and outside of the county accepted road rights of way as shown on the plat of this subdivision.
7. NOTICE: Any pipe, fence, wall, building, pool, patio, planting, stored material, excavation, fill, or other construction, improvement, addition to, or alteration of the land within a drainage easement in this subdivision requires the prior written approval of the County Drainage Board.

NOTES
 Owners of Lots 17, 18, and Lots 11,12,13,14, and 15 (Ashwood Phase I BQ P17) shall share in the cost of maintaining the lake, dam, and appurtenances thereto, and maintain liability insurance; and have exclusive control of the use of said lakes as designated by covenants of this plat. No permanent structures, above or below ground, may be constructed closer than 50 feet to said lake.

Erosion control: Slopes of 0 to 6% shall be mulched and seeded, i.e. rye, red top, and wheat (which will be used primarily for fall planting) within 45 days of disturbance of soil and must remain in place until final grading and shaping. Slopes more than 6% shall have straw bales and/or erosion blankets in place within 5 days of disturbance of soil and must remain in place until final grading and seeding.

All Lot corners marked with 5/8" Iron Pin except as noted
 All utilities available at site
 Drainage Plans were approved on March 7, 1998
 Street Plans were approved on March 7, 1998
 Primary approval on February 4, 1998

Site is partially within the 100 Year Flood Zone (Zone A9) according to FIRM Map Panel Number 180256 0025 C dated August 5, 1991. Lowest Finished Floor Elevation, including basements and attached garages, is 385.5. The Flood Protection Grade (F.P.G.) is shown on each lot.



We, the undersigned owners of the real estate shown and described hereon, do hereby as shown plat and subdivide said real estate and designate same as ASHWOOD PHASE IA

All streets within the plat are dedicated to the public. Building setback lines are established as shown on the plat between which lines and the property of the street there shall not be erected or maintained any building or structure. Strips of ground marked "P.U. Easement" are reserved for the use of public utilities. Owners of lots shall take title subject to the rights of the public utilities in said strips of ground. Strips of ground marked "Drainage Easement" are reserved for surface water and/or subsurface water drainage. No structure shall be erected or maintained in said strips of ground. Further, no bushes, shrubs, trees, or any other obstruction that would impede the flow of surface water shall be permitted in said strips of ground. Each lot owner shall be responsible for maintenance (cutting grass and weeds, and removing any obstructions to water flow) of that portion of the drainage channels or swales on their lots.

Strips of ground, of the width shown on this plat and marked "Public Utility Easement", are hereby dedicated to public utilities for the installation, maintenance, operation, enlargement and repair of utility facilities, whether above ground or below ground, with the right to trim or remove at the discretion of the public utility, trees, overhanging branches, bushes, underbrush, and obstructions. No structure other than said utility facility shall be located within said strips of land and any fence located within said strips of land is subject to removal by a public utility, without liability, in the use of said easements by said utility.

Strips of ground marked "Drainage Easement" are dedicated for surface water and/or subsurface water drainage; provided however, that public utilities are hereby permitted to cross such Drainage Easements with public utility facilities, and provided that such facilities are not placed in such manner as to impede the flow of water and further provided that such drainage easements may be used for ingress and egress and temporary staging areas for work by public utilities.

Jack R. Davis
 Jack R. Davis
 414 Hollybush Lane
 Evansville, Indiana 47715

Norma J. Davis
 Norma J. Davis

NOTARY CERTIFICATE
 STATE OF INDIANA } SS
 COUNTY OF VANDERBURGH }
 Before me, the undersigned notary public for Vanderburgh County, State of Indiana, personally appeared the above signed owners of the real estate shown and described hereon and acknowledged the execution of this plat to be their voluntary act and deed.

Witness my hand and seal this 7th day of July, 1999.

My commission expires 2/1/2003 Notary Public Barbara A. Pappas
 Resident of Vanderburgh County Printed Barbara A. Pappas

A.P.C. CERTIFICATE
 Under the authority provided by Acts of 1981, Public Law No. 309, and enacted by the General Assembly of the State of Indiana, this plat has been given Primary approval by the Area Plan Commission of Evansville and Vanderburgh County on FEB. 4, 1998.

Plat Release July 6, 2000
 President Mark Fozz
 Executive Director Barbara P. Cunningham

SURVEYORS CERTIFICATE
 I, Billy T. Nicholson, hereby certify that I am a Land Surveyor, licensed in compliance with the laws of the State of Indiana and further certify that this plat correctly represents a survey completed by me, and that all monuments shown exist at locations as noted; that this survey was made in accordance with Title 864, Article 1.1, Chapter 8, Section 1 through 34 of the Indiana Administrative Code and accordingly under my supervision. This is a class "B" survey with a theoretical uncertainty of 0.25 feet as determined by Sub-Section 7d, Section 7 of subject code.

Billy T. Nicholson
 Billy T. Nicholson IN No. 7964 Date 7/7/2000

1830-A W. Franklin Street - Evansville, Indiana 47712 - (812)424-2938

Ap# 3-S-98
 Q-82