

Part of the East Half of the Northeast Quarter of Section Twenty-six (26), Township Five (5) South, Range Eleven (11) West, lying in Vanderburgh County, Indiana being more particularly described as follows:

Beginning at a point in the center of Schaeffer Road, which point is North 00 degrees 00 minutes 55 seconds East 812.25 feet from the Southeast corner of said half quarter section: from said point of beginning thence continue North 00 degrees 00 minutes 55 seconds East a distance of 395.0 feet; thence North 89 degrees 55 minutes 36 seconds East a distance of 535.61 feet; thence North 89 degrees 55 minutes 36 seconds East a distance of 535.61 feet to the centerline of a ditch; thence South 05 degrees 32 minutes 15 seconds West along said centerline of said ditch a distance of 251.14 feet; thence continue along centerline of said ditch South 26 degrees 10 minutes 09 seconds East for 161.53 feet; thence South 89 degrees 55 minutes 36 seconds West 582.72 feet to the point of beginning.

BENTSEN SUBDIVISION

86-13021

OWNER'S CERTIFICATE

We, the undersigned Owner of the real estate shown and described hereon, do hereby lay-off, plat and subdivide said real estate, as shown, and designate it as

BENTSEN SUBDIVISION

All streets and alleys shown and not heretofore dedicated, are hereby dedicated to the public. Front and side yard building setback lines are hereby established as shown on this plat, between which lines and the property lines of the street, there shall be erected or maintained no buildings or structures.

Strips of ground of the width as shown on this plat and marked "easement" are hereby reserved for the use of public utilities for the installation of water, sewer mains, surface water drainage, poles, ducts, lines and wires, subject at all times to the proper authorities and to the easement herein reserved. No structures are to be erected or maintained upon said strips of land, but owners in this subdivision shall take their titles subject to the rights of the public utilities.

Arthur Bentsen
ARTHUR BENTSEN

Nicole Bentsen
NICOLE BENTSEN

NOTES:

These notes are required by the Area Plan Commission.

- Utilities:** Electric is available at the site and water is available from the German Township Water District
- Flood:** By using FIRM Panel 75 of 100, dated March 19, 1982, for Vanderburgh County, Indiana and by using the last elevation of 378.0, which is listed at the limits of the detailed study at Allen Lane. From this point the 378.0 elevation was pro-rated to the North to arrive at an elevation of 398.0. The proration was determined by subtracting the next lower elevation divided by the distance between to two points.
- Soil:** Stendal Silt Loam, 0 to 2 percent slopes, slow run-off, according to the Soil Survey of Vanderburgh County, Indiana.
- Erosion Control:** The disturbed areas shall be mulched and seeded, i.e., rye, red top, and wheat (which will be used primarily for fall planting) within 45 days of disturbance of soils and must remain in place until final grading and shaping.
- Zoning:** The zoning at this site, as well as the adjoining properties is agricultural.
- Owner and Developer:** Dr. Arthur and Mrs. Nicole Bentsen 350 W. COLUMBIA ST. EVANSVILLE 47710
- Engineer and Surveyor:** Sam Biggerstaff 1270 MAXWELL AVE 47711

NOTARY CERTIFICATE

STATE OF INDIANA)

) SS:

COUNTY OF VANDERBURGH)

Before me, the undersigned Notary Public of Warrick County, State of Indiana, personally appeared the above signed owner and subdivider of the real estate described hereon and acknowledged the execution of this plat to be his voluntary act and deed.

WITNESS my hand and seal this 3 day of June, 1986.

My commission expires:

July 4, 1986


Resident of Warrick County

Doris Jean Jackson
Notary Public
DORIS JEAN JACKSON
Printed

SURVEYORS CERTIFICATE

I, Sam Biggerstaff, hereby certify that I am a Registered Land Surveyor, licensed in compliance with the laws of the State of Indiana, and further certify that this plat correctly represents a subdivision as created by me, and that all monuments shown exist at the locations noted.

May 21, 1986
Date



Sam Biggerstaff
Sam Biggerstaff-L5
Indiana Reg. No. 9838




A.P.C. CERTIFICATE

Under the authority provided by the Acts of 1981, Public Law No. 309, and enacted by the General Assembly of the State of Indiana, this plat has been given SECONDARY APPROVAL by the AREA PLAN COMMISSION of EVANSVILLE and VANDERBURGH COUNTY at a meeting held on JUNE 5, 1986.

Sam Miller
President

Barbara L. Cunningham
Executive Director
Barbara L. Cunningham
Executive Director

Plat Release JUNE 5, 1986



RECEIVED FOR RECORD

at 3:08 P.M.

JUNE 5 1986

Plat Book N

Page 10

BOB STEELE, RECORDER
VANDERBURGH COUNTY

JULY ENTERED FOR TAXATION
JUN 05 1986

Alice McBride AUDITOR

3043

N-10

0 = DENOTES 3/8" IRON PIPE